

CALIFORNIA BUILDING STANDARDS COMMISSION
GREEN BUILDING
WORKSHOP
May 31st, 2016 - Agenda Item 4c

DRAFT EXPRESS TERMS for the 2016
CALIFORNIA GREEN BUILDING STANDARDS CODE,
(CALGreen), PART 11,
CALIFORNIA BUILDING STANDARDS CODE,
TITLE 24, CALIFORNIA CODE OF REGULATIONS

Proposed code language for the 2016 Intervening Code Adoption Cycle

LEGEND FOR EXPRESS TERMS

1. New California amendments: All such language appears underlined.
2. Repealed text: All such language appears in ~~strikeout~~.
[Information for the reader is bracketed and in red italics]

5.408.1.3 Waste Stream Reduction Alternative

- **Statement of specific purpose, problem, rationale and benefits:**

CBSC is proposing to amend the language for the Waste Stream Reduction Alternative calculation by changing the 2 pounds per square foot (PSF) requirement to 1.4 PSF. This amendment is necessary to align the 2015 triennial code update where BSC changed the regulation verbiage from 50% to 65% but did not change the corresponding 2 pounds per square foot (PSF) requirement to 1.4 PSF required to achieve the 65% rate.

CALRecycle allows 4 PSF for construction waste in nonresidential occupancies and the 2 PSF met the 50% requirement. Since the 50% was changes to 65% the 2 PSF needed to be adjusted to 1.4 PSF to align with the new requirement.

...

SECTION 5.408 CONSTRUCTION WASTE REDUCTION, DISPOSAL AND RECYCLING

5.408.1 Construction waste management. . .

5.408.1.1 Construction waste management plan . . .

5.408.1.2 Waste management company . . .

5.408.1.3 Waste stream reduction alternative. The combined weight of new construction disposal that does not exceed ~~two~~^{1.4} pounds per square foot of building area may be deemed to meet the 65 percent minimum requirement as approved by the enforcing agency.