

# 2022 CFC: FA SYSTEM; PI RESPONSIBILITIES— CONTROL FUNCTIONS (BATTERIES)

- PI Verification of FA System.
  - ✓ Ensure date of manufacture (month/year) is clearly noted on batteries.
  - ✓ Operational Tests: Observe the 5-minute test in alarm mode for horn/strobes; 15 minutes for speaker/strobes (voice evacuation).

Removed "24 hours on battery test" due to [OSFM CI 25-03](#). DSA does not require disconnecting power for 24 hours prior to commencing battery tests.



# 2022 CFC: FA SYSTEM; INSPECTION, TESTING, DOCUMENTATION (cont'd)

- PI Verification of Inspection/Testing/Documentation. (cont'd)
  - ✓ System operational tests completed:
    - 5-minute alarm duration for systems with horn-strobes.
    - 15-minute alarm duration for emergency voice alarm systems (speaker-strobes).
  - ✓ For EV/ACS systems, microphone in the administration area is accessible.
  - ✓ Power to FACU is 'on' and does not indicate system trouble conditions.

Removed "24-hour battery test and alarm duration completed" due to [OSFM CI 25-03](#).  
DSA does not require disconnecting power for 24 hours prior to commencing battery tests.