

#### STATE OF CALIFORNIA DEPARTMENT OF GENERAL SERVICES GENER

## REAL ESTATE SERVICES DIVISION PROJECT MANAGEMENT AND DEVELOPMENT BRANCH

## **PROJECT MANUAL – Book 2 of 2**

**APPENDICES** 

FOR:

OES SECURITY UPGRADES

GOVERNOR'S OFFICE OF EMERGENCY SERVICES

MATHER, SACRAMENTO COUNTY, CALIFORNIA

Jenny Li, Project Director West Sacramento, California

Designed By: State of California

October 1, 2025

000000000009324

#### **DOCUMENT 00 01 10**

#### **TABLE OF CONTENTS**

#### BOOK 1

#### PROCUREMENT AND CONTRACTING REQUIREMENTS GROUP

#### **DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS**

#### **INTRODUCTORY INFORMATION**

Document	00 01 01 00 01 05 00 01 10 00 01 15	Pages Project Title Page	
BIDDING F	REQUIREMEN		
Document Appendix Document	00 21 00 00 21 00.01	Invitation for Bids1 through 3Instructions to Bidders1 through 8Request for Bidding Interpretation1 onlySupplementary Instructions to Bidders1 onlyDVBE Participation Program Requirements1 through 3	
	00 41 00 00 43 13 00 43 16 00 45 46	Bid Form (Sample)	
CONTRACTING REQUIREMENTS			
Document	00 52 00 00 61 13 00 61 14 00 63 63 00 72 00 00 73 00	Agreement (Sample)	

#### **SPECIFICATIONS GROUP**

RESDMSTR: 6/20/2025

#### **GENERAL REQUIREMENTS SUBGROUP**

#### **DIVISION 01 - GENERAL REQUIREMENTS**

Section	01 10 00	Summary1 through	5
	01 21 00	Allowances1 through	2
	01 25 00	Substitution Procedures1 through	2

		Payment Procedures	
	01 31 00	Project Management and Coordination	•
	01 31 25	Web-based Project Management System	
	01 32 00	Construction Progress Documentation	
	01 32 33	Photographic Documentation	
	01 33 00	Submittal Procedures	
	01 33 29.08	Buy Clean California Act Requirements	
	01 35 16	Alteration Project Procedures	
	01 40 00	Quality Requirements	
	01 50 00	Temporary Facilities and Controls	•
	01 60 00 01 73 00	Product Requirements	
	01 73 00	Execution	
Form	01 74 19	Construction Waste Management and Disposal	
FOIIII	01 74 19.01	Waste Management Report	
Section	01 74 19.02	Recycled Content Certification	
Form	01 74 20.01	Recycled Content Certification Worksheet (Example)	
1 01111	01 74 20.01	State Agency Buy Recycled Campaign Procurement Summary (Ex	
	017420.02		
Section	01 75 00	Starting and Adjusting	
0000011	01 77 00	Closeout Procedures	l through 12
Form	STD 817	Prime Contractor's Certifications – DVBE Subcontractor Report1	
	01 77 00.01	Contractor's Certification of Small Business Participation	
	01 77 00.02	Contractor' Certification of Small Business Participation	•
Section	01 79 00	Demonstration and Training	•
		ION SUBGROUP	
DIVISION	02 – EXISTINO	GCONDITIONS	
Section	02 41 19	Selective Demolition	. 41
Section	02 11 10		through 4
	03 – CONCRE	ETE	tnrougn 4
		Concrete Forming and Accessories  Concrete Reinforcing  Cast-in-Place Concrete	I through 3
DIVISION (	03 – CONCRE 03 10 00 03 20 00 03 30 00	Concrete Forming and Accessories	I through 3
DIVISION ( Section	03 – CONCRE 03 10 00 03 20 00 03 30 00	Concrete Forming and Accessories	I through 3
DIVISION ( Section	03 – CONCRE 03 10 00 03 20 00 03 30 00 04 – MASONF	Concrete Forming and Accessories	I through 3 I through 3 I through 8
DIVISION ( Section  DIVISION ( DIVISION ( Section	03 – CONCRE 03 10 00 03 20 00 03 30 00 04 – MASONF 05 – METALS 05 50 00	Concrete Forming and Accessories	I through 3 I through 3 I through 8
DIVISION (	03 – CONCRE 03 10 00 03 20 00 03 30 00 04 – MASONF 05 – METALS 05 50 00	Concrete Forming and Accessories	I through 3 I through 3 I through 8
DIVISION ( Section  DIVISION ( Section  DIVISION ( DIVISION ( DIVISION ( DIVISION (	03 – CONCRE 03 10 00 03 20 00 03 30 00 04 – MASONF 05 – METALS 05 50 00 06 – WOOD, F	Concrete Forming and Accessories  Concrete Reinforcing  Cast-in-Place Concrete  RY (NOT USED)  Metal Fabrications  PLASTICS, AND COMPOSITES (NOT USED)	I through 3 I through 3 I through 8
DIVISION ( Section  DIVISION ( Section  DIVISION ( DIVISION ( DIVISION ( DIVISION ( DIVISION ( DIVISION (	03 – CONCRE 03 10 00 03 20 00 03 30 00 04 – MASONF 05 – METALS 05 50 00 06 – WOOD, F 07 – THERMA	Concrete Forming and Accessories  Concrete Reinforcing  Cast-in-Place Concrete  RY (NOT USED)  Metal Fabrications  PLASTICS, AND COMPOSITES (NOT USED)  LL AND MOISTURE PROTECTION (NOT USED)	I through 3 I through 3 I through 8
DIVISION ( Section  DIVISION ( DI	03 – CONCRE 03 10 00 03 20 00 03 30 00 04 – MASONF 05 – METALS 05 50 00 06 – WOOD, F 07 – THERMA 08 – OPENING	Concrete Forming and Accessories  Concrete Reinforcing  Cast-in-Place Concrete  RY (NOT USED)  Metal Fabrications  PLASTICS, AND COMPOSITES (NOT USED)  AL AND MOISTURE PROTECTION (NOT USED)  GS (NOT USED)	I through 3 I through 3 I through 8

RESDMSTR: 6/20/2025

Section	11 12 00	Parking Control Equipment	.1 through 7		
DIVISION	DIVISION 12 – FURNISHINGS (NOT USED)				
DIVISION	13 – SPECIAI	L CONSTRUCTION			
Section	13 34 23.16	Fabricated Control Booths	1 through 8		
DIVISION	14 – CONVE	YING EQUIPMENT (NOT USED)			
DIVISION	15 – RESER\	/ED (NOT USED)			
DIVISION	16 – RESER\	/ED (NOT USED)			
DIVISION	17 – RESER\	/ED (NOT USED)			
DIVISION	18 – RESER\	/ED (NOT USED)			
DIVISION	19 – RESER\	/ED (NOT USED)			
FACILITY	SERVICES S	SUBGROUP			
DIVISION	20 – RESER\	/ED (NOT USED)			
DIVISION	21 – FIRE SU	JPPRESSION (NOT USED)			
DIVISION	22 – PLUMBI	NG (NOT USED)			
DIVISION	23 – HEATING	G, VENTILATING, AND AIR CONDITIONING (HVAC) (NOT USED	))		
DIVISION	24 – RESER\	/ED (NOT USED)			
DIVISION	25 – INTEGR	ATED AUTOMATION (NOT USED)			
DIVISION	26 – ELECTR	RICAL			
Section	26 05 19 26 05 23 26 05 26 26 05 29 26 05 33 26 05 53 26 22 00 26 24 16 26 27 26 26 28 16 26 56 19	Low-Voltage Electrical Power Conductors and Cables Control-Voltage Electrical Power Cables Grounding and Bonding For Electrical Systems Hangers and Supports For Electrical Systems Raceways and Boxes For Electrical Systems Identification For Electrical Systems Low Voltage Transformer Panelboards Wiring Devices Enclosed Switches and Circuit Breakers LED Exterior Lighting	1 through 10 1 through 6 1 through 4 1 through 12 1 through 8 1 through 6 1 through 7 1 through 4 1 through 7		
DIVISION 27 – COMMUNICATIONS					
Section	27 05 28 27 05 53 27 15 23	Pathways For Communications SystemsIdentification For Communications SystemsCommunications Optical Fiber Horizontal Cabling	.1 through 3		

RESDMSTR: 6/20/2025

#### DIVISION 28 – ELECTRONIC SAFETY AND SECURITY

Section	28 05 13 28 05 26 28 05 28 28 23 00	Conductors and Cables For Electronic Safety and Security	
DIVISION	29 – RESERV	/ED (NOT USED)	
SITE AND	INFRASTRU	CTURE SUBGROUP	
DIVISION	30 – RESERV	(ED (NOT USED)	
DIVISION	31 – EARTHV	VORK	
Section	31 10 00 31 20 00 31 21 00 31 23 19	Site Clearing	
DIVISION	32 – EXTERIO	OR IMPROVEMENTS	
Section	32 11 00 32 12 16 32 13 13 32 13 15 32 13 18 32 17 23 32 17 26 32 21 19.13	Pavement Base Course	
DIVISION	33 – UTILITIE	S	
Section	33 41 00	Storm Utility Drainage Piping1 through 9	
DIVISION 34 – TRANSPORTATION (NOT USED)			
DIVISION 35 – WATERWAY AND MARINE CONSTRUCTION (NOT USED)			
DIVISION 36 - RESERVED (NOT USED)			
DIVISION 37 – RESERVED (NOT USED)			
DIVISION 38 – RESERVED (NOT USED)			
DIVISION 39 – RESERVED (NOT USED)			
PROCESS EQUIPMENT SUBGROUP (NOT USED)			

### BOOK 2

## **REFERENCE DOCUMENTS**

#### INTRODUCTORY INFORMATION

RESDMSTR: 6/20/2025

			Pages
Document	00 01 10	Table of Contents	1 through 5
APPENDIC	CES		
	Appendix A	Subsurface Utility Management: Utility Location Report	1 through 22
		Utility Exhibit Map	
	Appendix C	Potholing Test Hole Data Report	1 through 5
	Appendix D	Existing Conduits Push Camera & Utility Locating Report	1 through 5
	Appendix E	Geotechnical Report	1 through 20
		Due Diligence Survey Map	
		Topographic Survey	
		Easement Review Letter from PG&E	

**END OF DOCUMENT** 

July 20, 2022

Subject: Subsurface Utility Management: Utility Location Report

OES Site – 3650 Schriever Mather, CA

This report is intended to serve as a preliminary assessment of the underground utilities detected on the given and agreed upon site. The findings documented within are intended for the specific client and purpose listed. All assets listed are Quality Level B at best, in accordance with the American Society of Civil Engineers' Standard for Subsurface Utility Engineering (link here). As such, this report may not be entirely conclusive as the complete condition of the site. Various forms of geophysical interference as well as material type may lead to certain utilities (HDPE, PVC/ABS, Vitrified Clay Pipe, Non-Reinforced Concrete, et cetera) not being able to be detected via approved methods. It is the recommendation of Psomas that those responsible for excavation conduct necessary Quality Level A assessments of the site before critical excavation. As always, any methods of excavation used after delivery of this report should be done with extreme caution. This report is not a replacement for 811, or any other One-Call service.

Respectfully,

Tom Pilarski, PLS

Vice President

#### A: TOOLS

A.1: Ground Penetrating Radar (GPR) – A Sensors and Software Noggin system with a 400 MHz antenna was used to search for and detect utilities and subsurface anomalies. GPR works by emitting a low amplitude (energy) pulse of electromagnetic radiation across a narrow distribution in the radio wave area of the light spectrum. The waves are reflected back or transmitted through depending on the change in dielectric of the soils and underground utilities. The returning signal is then interpreted by the technician and potential features are tagged.

A.2: Line Locator – A Radio Detection RD 8100 unit was used in various modes (e.g.: passive, and induction via clamp, leads, or transmitter). All methods rely on the same principles. Wherever there is flow, whether it be water, electricity, oil, or nearly any other substance, there will be electromagnetic flux. This flux bleeds off in a known and uniform pattern and can be measured by the receiver of the line locator. If naturally occurring flux is not sufficient, a line will be induced at a specific frequency and the resultant flux can be traced.

A.3: Metal Detector – A Schonstedt Maggie was used to detect metallic objects that may or may not have been detectable to previously listed methods. The metal detector works by emitting a specific alternating magnetic field. When metallic objects encounter this field, they distort and bend the field. These distortions are then displayed to the technician.

#### **B: METHODS**

- B.1: Visual Inspection All visible or marked utilities were first identified and followed for their duration above ground. Line size, service type, material, trend, and other factors are noted for further tracing. Trenches may also be visible, as an indication of where utilities may be buried.
- B.2: Line Locating All previously identified lines from previous steps were traced using passive and/or active methods. Lines were marked according to state standards, being careful to use appropriate colors and delineating symbols.
- B.3: GPR The agreed upon site was scanned along both relative cardinal axes across critical areas. Any anomalies were marked and confirmed with other methods.

## C: SCOPE

C.1: Scope is to detect utilities within the Office of Emergency Services facility, located in Mather CA, and show below outlined in blue, cyan and red hatched areas in Figures A, B and C.




Figure A




Figure B



Figure C

# D: FINDINGS – COLOR CODE USED IS ESTABLISHED BY THE AMERICAN PUBLIC WORKS ASSOCIATION (APWA)

D.1: Electrical Lines –	Red
D.2: Telecommunication Lines –	Orange
D.3: Gas/Oil/Steam/HC Lines –	Yellow
D.4: Water Lines –	Cyan/Blue
D.5: Storm Drain and Sewer Lines -	Green
D.6: Unknown/Undefined Utilities and Features –	Pink

### E: Sites and Utilities Detected

#### E.1 Location 1


The below exhibit captures all utilities detected within the location area(s) for detection activities performed on May 31 through June 3, and June 9 through June 10, 2022. Refer to the following sections for a description of each utility type. To facilitate reference to individual lines, lines have been labeled and numbered as described in this report in the associated KMZ file.



**Location 1 - All Utilities Detected** 

E.1.1 Electrical: At this location fourteen electrical lines were detected. The first line begins at a utility pole on the east side of Old Placerville Road, north of the southwesterly driveway. This line travels easterly across the main drive aisle and southwesterly parking lot to what appears to be a transformer southwest of Building C, at an approximate depth between 48" and 60". The second line begins at a light pole on the south side of the main drive aisle, near the southwesterly driveway. This line travels southerly then northeasterly to the northwest corner of Building C, at an approximate depth of 30". The third line begins at a light pole at the northwest corner of the southwesterly-most driveway. This line travels southeasterly to a light pole at the southwest corner of the parking lot, travels northeasterly to a light pole at the south side of the central landscaped median of the parking lot, then travels northwesterly to a light pole at the north side of this landscaped median. At the pole that is at the south side of the medial, this line wyes and travels southeasterly to a light pole at the southeast corner of this parking lot. This line travels at an approximate depth of 30". The fourth line begins at what appears to be a transformer southwest of Building C. This line travels northeasterly to Building C, at an approximate depth of 48". The fifth line begins in the median between Building C and the southwesterly-most parking lot, south of electrical line four (described above). This line travels northerly to Building C. The sixth line begins at what appears to be a cabinet in the median between Building C and the southwesterly-most parking lot, south of electrical line five (described above). This line travels northeasterly to Building C, at an approximate depth of 31". The seventh line begins at the west side of Building C. This line travels southeasterly then easterly along the drive aisle around the south side of Building C, then travels northeasterly across the parking lots east of Building C to the solar panel arrays that are southeast of Building B, then wyes. The first wye segment travels southeasterly then northeasterly through the solar panel arrays south of the main drive aisle and continues northeasterly across the southeasterly most parking lot to the easterlymost planter, then travels southeasterly along the planter. At the second solar panel from the west, this segment tees, travels southeasterly then northeasterly through the remaining solar panels, and continues northeasterly to the east-most landscaped median in the southeasterly parking lot, then travels northwesterly/southeasterly along this median connecting a series of light poles. The second wye segment travels northeasterly across the main drive aisle to the solar arrays east of Building B, travels northeasterly along the south side of these solar arrays to the northeasterly most solar arrays, then travels northwesterly through the northeasterly most solar arrays. At the southwesterly-most solar panel in the arrays east of Building B, this line tees and travels northwesterly to an electrical box in the landscaped median on the west side of the shorter

section of solar arrays, travels northeasterly then northwesterly to the northwest-most solar panel, then tees and travels northeasterly to a light pole in the landscaped median south of the northeasterly driveway, and travels southwesterly through a series of light poles along the back of sidewalk on the north side of Building B. At the northwest-most solar panel, this tee segment tees and travels northwesterly across the northerly parking lot, then tees and travels southwesterly through a series of light poles along the north side of the north parking lot, and northeasterly across the northeasterly driveway to a light pole north of the northeasterly-most parking lot, then southeasterly to a light pole on the south side of the northeasterly-most parking lot. This line travels at an approximate depth of 48" between Building C and the solar arrays, and an approximate depth between 30" and 40" in and around the solar arrays and parking lots. The eighth line begins at a light pole in the southerly most landscaped planter, approximately 100' east of the southeast corner of Building C. This line travels northeasterly, through a series of light poles, along the south landscaped planter and south-most row of parking stalls, to a light pole at the southeast corner of the facility. Approximately 115' southwest of the southeast corner of the facility, this line tees and travels northwesterly through the central landscaped median of the southeasterly-most parking lot and continues northwesterly along the drive aisle to a point near the northeasterly driveway, where our locator lost signal on this line. This line travels at an approximate depth between 30" and 40". The ninth line begins at the landscaped median in the parking lot that is southeast of Building B and travels northwesterly/southeasterly along this median. The tenth line begins at the west-most landscaped median at the southeasterly-most parking lot and travels northwesterly/southeasterly along this median. The eleventh line begins at the southeast solar panel of the arrays directly northeast of Building B. This line travels northeasterly to a light pole in the southeasterly-most round landscaped median between the two drive aisles that travel to the northeasterly driveway. The twelfth line begins at the solar panel north of the panel where electrical line eleven (described above) begins. This line travels northeasterly to a light pole in the central round landscaped median between the two drive aisles that travel to the northeasterly driveway. The thirteenth line begins at the solar panel that is north of the panel where electrical line twelve (described above) begins. This line travels northeasterly to the northerly landscaped median between the two drive aisles that travel to the northeasterly driveway, then travels northwesterly to the concrete median at the northeasterly driveway. The fourteenth line begins at the concrete median at the northeasterly driveway. This line travels northeasterly and southwesterly across the east and west driveway drive aisles.



Location 1 – Electrical

E.1.2 Telecommunication: At this location four communication lines were detected. The first line begins in the east side of Old Placerville Road, north of Schriever Avenue. This line travels southerly along the east shoulder of Old Placerville Road to the southerly limits of the utility detection area, at an approximate depth of 48". The second line begins at a utility pole that is north of the southwesterly driveway. This line travels southerly along the sidewalk to the southerly limits of the utility detection area. The third line begins in the field south of the OES facility, east of Old Placerville Road, at the southerly limits of the utility detection area. This line travels northerly to the south side of the southerly fence line, then travels easterly for approximately 85' feet where our locator lost signal on this line. The third line begins at the west side of Building C. This line travels southeasterly to the drive aisle, then travels easterly then northeasterly, across the parking lots east of Building C, to the north side of the central drive aisle, travels northeasterly to the south side of the northeasterly-most solar panel arrays, then travels northwesterly to the north side of this solar panel array. At the southwest side of the solar panel array that is east of Building B, this line tees and travels northwesterly to the northwest side of this solar panel array. This line travels at an approximate depth between 31" and 48".



**Location 1 – Communication** 

<u>E.1.3 Gas/Oil/Steam/HC</u>: At this location two gas lines were detected. The first line begins on the west side of Building C. This line travels southwesterly across the drive aisle, travels northwesterly then northeasterly to the north side of Building C, then travels northwesterly to the south side of Building A, at an approximate depth of 36". The second line begins in Schriever Avenue. This line travels southeasterly along the westerly drive aisle at the northeasterly driveway and continues southeasterly across the facility to the southerly limits of the utility detection area, at an approximate depth between 40" and 48".



Location 1 - Gas

E.1.4 Water: At this location three water lines were detected. The first line begins in the northbound lanes of Old Placerville Road, north of the southwesterly driveway. This line travels southerly along Old Placerville Road, travels southeasterly to the dirt behind the sidewalk, then travels southerly to the southerly limits of the utility detection area. South of the southwesterly driveway, this line tees and travels easterly to the landscaped area south of the southwesterly driveway, then splits into three segments. Our locator noted they lost signal on these three segments near the westerly side of the landscaped area. The second line begins in the eastbound bike lane of Schriever Avenue. This line travels easterly/westerly along Schriever Avenue. Approximately 100' east of Old Placerville Road, this line tees and travels southerly to a valve assembly in the northwest corner of the OES facility property. The third line begins in the central northeasterly/southwesterly drive aisle, at a planter west of Building C. This line travels northerly then northeasterly along the drive aisle to a point approximately 90' east of the southeast corner of Building B. Our locator noted they lost signal on this line at the southwest and northeast ends of the line.



Location 1 - Water

E.1.5 Storm Drain / Sewer: At this location five storm drain lines were detected. The first line begins at the east side of Old Placerville Road, south of the southwesterly driveway. This line travels easterly along the southerly fence line to a catch basin at the south side of the southwesterly parking lot, then travels northeasterly to a landscaped median southeast of Building C. At the catch basin, this line wyes and travels northerly then northwesterly to a catch basin in the westerly drive aisle of the southwesterly parking lot, then tees. One segment travels northwesterly to a catch basin in the curb on the north side of the central drive aisle, and continues northwesterly. The other segment travels northeasterly to a catch basin in the easterly drive aisle of the southwesterly parking lot. The second line begins at a manhole in the central drive aisle between Building A, B and C. This line exits the manhole to the northeast to Building B, to the southwest to Building A, to the northwest between Buildings A and B, and to the southeast, traveling along the drive aisle on the east side of Building C, passing through a catch basin, and continuing southeast to the north side of the drive aisle that is south of Building C. At the catch basin, this line tees and travels southwesterly to Building C. The third line begins in the drive aisle that is south of Building C, approximately 115' east of the southeast corner of Building C. This line travels northeasterly along the drive aisle, passing through a series of catch basins, and continues to a catch basin south of the middle drive aisle at the southeasterly most parking lot, then travels northwesterly along this drive aisle to another catch basin. In the middle of this drive aisle, this line tees and travels northeasterly to the landscaped median between the parking stalls. The fourth line begins at a manhole in the traffic circle at the northwest side of the facility. This line exits the manhole to the northeast and to the east, traveling to catch basins in the median of the traffic circle; to the south traveling to Building A, and to the west, traveling through a catch basin north of Building A and continuing to a catch basin northwest of Building A. At the basin that is north of Building A, this line tees and travels southerly to the landscaped planter north of Building A. The fifth line begins at a manhole in Schriever Avenue, between the northwesterly and northeasterly driveways. This line travels northeasterly along Schriever Avenue, passes through two manholes near the northeasterly driveway, and continues northeasterly. At the westerly of the two manholes near the northeasterly driveway, this line wyes, travels southeasterly to a manhole in the westerly drive aisle of the northeasterly parking lot, continues southeasterly, passes through a manhole and continues southeasterly to a catch basin, then tees, connecting a series of catch basins throughout the solar panel arrays that are northeast of Building B. At the manhole that is in the northeasterly driveway, this line tees and

travels northeasterly and southwesterly along the northmost row of parking stalls, connecting a series of catch basins.



**Location 1 – Storm Drain** 

Three sewer lines were detected at this location. The first line begins in Old Placerville Road near the southwesterly driveway. This line travels northeasterly along the main drive aisle, passes through a clean out at the southwesterly driveway, passes through a manhole south of Building A, and continues northeasterly to a manhole south of Building B, then travels northwesterly to Building B. At the manhole south of Building A, this lien travels northwesterly into the dirt west of Building A. The second line begins at a manhole in the northeasterly-most parking lot. This line exits the manhole to the northwest toward Schriever Avenue; to the northeast toward the tennis courts, and to the southeast to northeasterly-most solar panel arrays, where our locator lost signal on this line. Our locator noted that there appeared to be no flow in this manhole. The third line begins at a manhole in the southeasterly-most parking lot. This line exits the manhole to the northeast, to the east, and to the southeast. Our locator noter this line appears to be abandoned.



**Location 1 – Sewer** 

<u>E.1.6 Unknown/Undefined Utilities and Features</u>: At this location four unknown lines were detected. The first line begins in the landscaped planter on the west side of the northeasterly driveway. This line travels southerly across the drive aisle to the adjacent solar panel array, at an approximate depth of 35". The second line begins in the landscaped area on the southeast side of Building B. This line travels east southeasterly to the solar panel arrays, then southeasterly to the southerly fence line. The third and fourth lines begin in the westerly drive aisle of the southeasterly-most parking lot. These lines travel northeasterly/southwesterly across this drive aisle.




Location 1 - Unknown

<u>E.1.7 Additional Notes:</u> Our locator observed two boxes in the dirt west of Building A but were unable to obtain a signal on any lines in these boxes. Our locator also observed an electrical box in the concrete pathway east of the water valve assembly at the northwest corner of the facility but was unable to obtain a signal on any lines in this box.



Location 1 – Additional Notes





Roseville, CA 95678 (916) 788-8122 (916) 788-0600 (FAX)


MATHER


3650 SCHRIEVER AVENUE SACRAMENTO COUNTY

6CAL212503 CALIFORNIA









## TEST HOLE DATA REPORT

TR1 TEST HOLE NO: TEST HOLE DATE:\_ 10/26/2022 T2utility engineers

CLIENT TEST HOLE NO: SUE CREW/TRUCK NO: LC/JWII/550603

CITY,COUNTY: MATHER, SACRAMENTO,

LOCATION/INTERSECTION:

SW GATED ENTRANCE

PROJECT NO:\_ CA16700125 CLIENT: PSOMAS
PROJECT: DGS CAL OES SITE

5622 Research Drive Suite A Huntington Beach, California 92649 TEL:714.487.5780 www.T2ue.com


MAP








**CROSS SECTION - NOT TO SCALE** 



TEST HOLE - UTILITY - FACING SW



DISCLAIMER: ADDITIONAL MATERIAL AND/OR UTILITIES MAY EXIST BELOW APPARENT BOTTOM

STATION

UTILITY DESCRIPTION		REFERENCE MARKER	
	111111111111111111111111111111111111111	NODTUNO	4.0

1969898.80' UTILITY TYPE NORTHING UNKNOWN

PLASTIC (PVC, PE, UTILITY MATERIAL HDPE) EASTING 6759977.05'

NORTHEAST -UTILITY DIRECTION SOUTHWEST **ELEVATION** 86.72'

UTILITY WIDTH (FIELD) 8.00" LOCATION

CENTER OF UTILITY UTILITY WIDTH (RECORD) MARKED BY NAIL & DISK

DEPTH FROM REFERENCE MARKER OFFSET

UNK

TOP OF UTILITY 4.00' OFFSET FROM

BOTTOM OF UTILITY

**ELEVATION OF UTILITY** 

APPARENT UTILITY OWNER

TOP OF UTILITY 82.72' APPARENT BOTTOM OF UTILITY

SURFACE

ASPHALT TYPE THICKNESS 4.00"

OPENED TRENCH BETWEEN CLIENT MARKS. FOUND AN 8-IN PVC WATERLINE AT -4.00FT.

NO OTHER UTILITIES FOUND TO REFUSAL AT -5.0FT.

REVISION NOTES:

REVIEWED DATE: CHECKED DATE: REVISION DATE:

REVIEWED BY CHECKED BY

## TEST HOLE DATA REPORT

TR2 TEST HOLE NO: TEST HOLE DATE: 10/25/2022 T2utility engineers

CLIENT TEST HOLE NO:\_ SUE CREW/TRUCK NO: LC/JWII/550603

> MATHER, SACRAMENTO, CITY, COUNTY: CA

LOCATION/INTERSECTION:

MAIN ENTRANCE

PROJECT NO:\_ CA16700125

CLIENT: PSOMAS
PROJECT: DGS CAL OES SITE

5622 Research Drive Suite A Huntington Beach, California 92649 TEL:714\_487.5780 www.T2ue.com






SITE PHOTO - FACING SW



**CROSS SECTION - NOT TO SCALE** 







DISCLAIMER: ADDITIONAL MATERIAL AND/OR UTILITIES MAY EXIST BELOW APPARENT BOTTOM

UTILITY DESCRIPTION		REFERENCE MARKER	
UTILITY TYPE	ELECTRIC	NORTHING	1970472.73'
UTILITY MATERIAL	CONCRETE	EASTING	6760534.59'
UTILITY DIRECTION	NORTHEAST - SOUTHWEST	ELEVATION	87.20'
UTILITY WIDTH (FIELD)	15.00"	LOCATION	WEST EDGE
UTILITY WIDTH (RECORD)		MARKED BY	ROD & CAP
APPARENT UTILITY OWNER	UNK	STATION	
DEPTH FROM REFERENCE MARKER		OFFSET	-
TOP OF UTILITY	0.90'	OFFSET FROM	
BOTTOM OF UTILITY	1.70'		

#### **ELEVATION OF UTILITY**

TOP OF UTILITY 86.30' APPARENT BOTTOM OF UTILITY 85.50'

#### SURFACE

TYPE NATURAL GROUND

THICKNESS

OPENED TRENCH BETWEEN CLIENT MARKS. FOUND A 15-IN WIDE RED CONCRETE ELECTRICAL DUCT BANK TOP AT -0.90FT AND BOTTOM AT -1.70FT.

#### REVISION NOTES:

REVIEWED DATE:	CHECKED DATE:	REVISION DATE:
REVIEWED BY:	CHECKED BY:	

## TEST HOLE DATA REPORT

TR2.1 TEST HOLE NO: TEST HOLE DATE:\_ 10/25/2022

PROJECT NO:\_



CLIENT TEST HOLE NO: SUE CREW/TRUCK NO: LC/JWII/550603

CITY,COUNTY: MATHER, SACRAMENTO,

LOCATION/INTERSECTION:

MAIN ENTRANCE

CLIENT: PSOMAS
PROJECT: DGS CAL OES SITE

5622 Research Drive Suite A Huntington Beach, California 92649 TEL:714.487.5780 www.T2ue.com

MAP


CA16700125



SITE PHOTO - FACING SW



**CROSS SECTION - NOT TO SCALE** 



TEST HOLE - UTILITY - FACING NW



DISCLAIMER: ADDITIONAL MATERIAL AND/OR UTILITIES MAY EXIST BELOW APPARENT BOTTOM

ITILITY DESCRIPTION	
UTILITY TYPE	

IRRIGATION

NORTHING

REFERENCE MARKER

1970473.84'

PLASTIC (PVC, PE, UTILITY MATERIAL HDPE)

EASTING

6760535.27'

UTILITY DIRECTION

NORTHEAST -SOUTHWEST 1.50"

UTILITY WIDTH (FIELD) UTILITY WIDTH (RECORD)

**ELEVATION** LOCATION

87.11' CENTER OF UTILITY

APPARENT UTILITY OWNER UNK MARKED BY STATION

OFFSET FROM

ROD & CAP

DEPTH FROM REFERENCE MARKER

OFFSET

TOP OF UTILITY 0.80'

BOTTOM OF UTILITY

**ELEVATION OF UTILITY** 

TOP OF UTILITY 86.31' APPARENT BOTTOM OF UTILITY

SURFACE

TYPE NATURAL GROUND

THICKNESS

OPENED TRENCH BETWEEN CLIENT MARKS. FOUND AN 1.5-IN PVC IRRIGATION PIPE AT -0.80FT.

REVISION NOTES:

REVIEWED DATE:

CHECKED DATE:

REVISION DATE:

REVIEWED BY CHECKED BY

#### TEST HOLE DATA REPORT

TR2.2 TEST HOLE NO: TEST HOLE DATE:\_ 10/25/2022



CLIENT TEST HOLE NO: SUE CREW/TRUCK NO: LC/JWII/550603

CITY,COUNTY: MATHER, SACRAMENTO,


LOCATION/INTERSECTION:

MAIN ENTRANCE GATE

PROJECT NO:\_ CA16700125

CLIENT: PSOMAS
PROJECT: DGS CAL OES SITE

5622 Research Drive Suite A Huntington Beach, California 92649 TEL:714.487.5780 www.T2ue.com




SITE PHOTO - FACING SW



**CROSS SECTION - NOT TO SCALE** 







6760540.09'

DISCLAIMER: ADDITIONAL MATERIAL AND/OR UTILITIES MAY EXIST BELOW APPARENT BOTTOM

TILITY DESCRIPTION	

#### REFERENCE MARKER

UTILITY TYPE NORTHING IRRIGATION 1970477.09'

PLASTIC (PVC, PE, UTILITY MATERIAL EASTING HDPE)

SOUTHEAST -UTILITY DIRECTION NORTHWEST **ELEVATION** 86.71'

UTILITY WIDTH (FIELD) 10.00" LOCATION CENTER OF UTILITY UTILITY WIDTH (RECORD) MARKED BY ROD & CAP

APPARENT UTILITY OWNER UNK STATION DEPTH FROM REFERENCE MARKER OFFSET

TOP OF UTILITY 0.60' OFFSET FROM

BOTTOM OF UTILITY

#### **ELEVATION OF UTILITY**

TOP OF UTILITY 86.11' APPARENT BOTTOM OF UTILITY

#### SURFACE

TYPE NATURAL GROUND

**THICKNESS** 

OPENED TRENCH BETWEEN CLIENT MARKS. FOUND FOUR PVC IRRIGATION PIPES AT -0.60FT. (1) 1-IN AND (3) 2-IN PIPES RUNNING TOGETHER.

#### REVISION NOTES:

REVIEWED DATE: CHECKED DATE: REVISION DATE:

REVIEWED BY CHECKED BY

#### TEST HOLE DATA REPORT

TEST HOLE NO: TR3 TEST HOLE DATE: 10/26/2022

PROJECT NO:\_



CLIENT TEST HOLE NO: SUE CREW/TRUCK NO: LC/JWII/550603

MAIN ENTRANCE GATE

MATHER, SACRAMENTO,

CITY, COUNTY

LOCATION/INTERSECTION:

5622 Research Drive Suite A Huntington Beach, California 92649 TEL:714.487.5780 www.T2ue.com

CLIENT: PSOMAS
PROJECT: DGS CAL OES SITE

MAP

CA16700125


#### SITE PHOTO - FACING SOUTH





**CROSS SECTION - NOT TO SCALE** 

**TEST HOLE - UTILITY - FACING SW** 





#### DISCLAIMER: ADDITIONAL MATERIAL AND/OR UTILITIES MAY EXIST BELOW APPARENT BOTTOM

JTILITY DESCRIPTION	
UTILITY TYPE	
UTILITY MATERIAL	

UTILITY DIRECTION

**EXPLORATORY** 

NONE

REFERENCE MARKER NORTHING **EASTING** 

1970491.63 6760529.87' 83.43'

LATHE

UTILITY WIDTH (FIELD)

**ELEVATION** LOCATION CENTER OF TRENCH

UTILITY WIDTH (RECORD)

MARKED BY

APPARENT UTILITY OWNER

STATION

DEPTH FROM REFERENCE MARKER TOP OF UTILITY

OFFSET

OFFSET FROM

**BOTTOM OF UTILITY** 

ELEVATION OF UTILITY

TOP OF UTILITY

APPARENT BOTTOM OF UTILITY

SURFACE

TYPE NATURAL GROUND

**THICKNESS** 

OPENED TRENCH BETWEEN CLIENT MARKS. FOUND NO UTILITIES DOWN TO -5.50FT WERE WE ENCOUNTERED WET SOIL THAT COULD NOT BE REMOVED WITH THE AIR-VACUUM. NAIL SET AT CENTER OF TR3.

REVISION NOTES:

REVIEWED DATE:

CHECKED DATE:

REVISION DATE:

REVIEWED BY:

CHECKED BY:



### APPENDIX D

CCTV PIPELINE INSPECTION

CONCRETE SCANNING

CONCRETE CUTTING

UTILITY LOCATING

Arizona – California – Florida – Texas

3801 Charter Park Ct. Ste. A, San Jose, CA 95136
Tel: 408.266.700 • Fax: 408.266-7050 • www.safe2core.com

Client: BKF Engineers
Jobsite:3650 Schriever Ave,

Mather, CA 95655

#### Push Camera & Utility Locating Services

#### 1. Project Overview

Our team was engaged by **BKF Engineers** to perform push camera inspection and utility locating services at **3650 Schriever Ave, Mather, CA 95655**. The work involved inspecting the interior of two existing 4" conduits running from an exterior utility box to a utility room in Building B, and marking the conduit route and depths above ground.

#### 2. Scope of Work

#### 1. Conduit Inspection

- Video camera inspection of two 4" conduits to assess their condition and determine reuse feasibility.
- o Conduits run from an exterior utility box into Building B's utility room.

#### 2. Utility Locating

- Used a sonde attached to the camera head for real-time location tracking.
- Marked the routing and approximate depths of the conduits on the ground surface.

#### 3. Methodology

#### 1. Camera Inspection

- Initiated the push camera from the exterior utility box.
- Advanced the camera 255 feet toward Building B until the camera could not negotiate the interior bend leading into the building.
- Conducted a second inspection from inside the utility room of Building B, pushing the camera 100 feet toward the exterior utility box.
- These two segments ensured the entire conduit length was recorded and inspected.

#### 2. Locating & Depth Measurement

- o A sonde on the camera head transmitted signals to our surface receiver.
- Depth readings were taken at regular intervals and marked on the surface.
- Average conduit depth was 3 feet, with some points measuring up to 3 feet 4 inches.



3801 Charter Park Ct. Ste. A, San Jose, CA 95136
Tel: 408.266.700 • Fax: 408.266-7050 • www.safe2core.com

# CCTV PIPELINE INSPECTION CONCRETE SCANNING CONCRETE CUTTING UTILITY LOCATING

Arizona - California - Florida - Texas

#### 4. Findings

#### 1. Conduit Condition

- Both conduits appear to be in generally good condition.
- Portions of each conduit contained standing water, which would need to be cleared prior to reuse.

#### 2. Conduit Routing & Depth

- The conduit routes were successfully traced and marked from the exterior box to the building interior.
- o The average depth was **3 feet**, varying up to **3 feet 4 inches** in certain sections.

#### 3. Reuse Feasibility

- o No major obstructions, cracks, or significant damage were observed.
- Minor debris and water accumulation should be addressed to ensure smooth cable or equipment pulls in the future.

#### 6. Deliverables

 Video Footage: Push camera videos documenting interior conditions of both conduits below:

#### Conduit 1 From Utility Box to Building B

https://dgscloud.box.com/s/zdlk025q8tki7cpechdn82x07jmv21s6

**Conduit 1 from Building B Towards Utility Box** 

https://dgscloud.box.com/s/2noraplnmbbhvfpnduf1e5umh8adq73x

Conduit 2 from Utility Box to Building B

https://dgscloud.box.com/s/g8dvgts9j1p3vws8zn6qxebwbfscs60c

**Conduit 2 from Building B towards Utility Box** 

https://dgscloud.box.com/s/46ab8sw2mt3a3bj1twek4yft82u9hs3x

Use links above to download video footage mp4 files.




3801 Charter Park Ct. Ste. A, San Jose, CA 95136
Tel: 408.266.700 • Fax: 408.266-7050 • www.safe2core.com

# CCTV PIPELINE INSPECTION CONCRETE SCANNING CONCRETE CUTTING UTILITY LOCATING

Arizona - California - Florida - Texas

Marked Routing: Visible surface markings indicating conduit paths.







## 3801 Charter Park Ct. Ste. A, San Jose, CA 95136 Tel: 408.266.700 • Fax: 408.266-7050 • www.safe2core.com

# CCTV PIPELINE INSPECTION CONCRETE SCANNING CONCRETE CUTTING UTILITY LOCATING

Arizona - California - Florida - Texas

• **This Report**: Summarizing the methods, findings, and recommendations for conduit reuse.

Prepared by:
Antonio Guzman
Safe2core, Inc





GEOTECHNICAL • ENVIRONMENTAL • MATERIALS

Project No. S2120-05-08 October 11, 2023

#### **VIA ELECTRONIC MAIL**

Lorenz A. Quinley Associate Architect Department of General Services 707 3rd Street, West Sacramento, California 95605 Lorenz.quinley@dgs.ca.gov

Subject: LIMITED GEOTECHNICAL INVESTIGATION

CALIFORNIA OFFICE OF EMERGENCY SERVICES

3650 SCHRIEVER AVENUE MATHER, CALIFORNIA

Mr. Quinley:

In accordance with Agreement No. 17496-B, Task Order No. 5 dated July 6, 2022 and our proposal dated June 1, 2022, we have prepared this limited geotechnical investigation report for the proposed security improvements to the existing facility entrance and exit drives at the California Office of Emergency Services (OES) facility located at 3650 Schriever Avenue in Mather, California. The approximate project location is shown on the Vicinity Map, Figure 1.

#### **PURPOSE AND SCOPE**

The purpose of our limited geotechnical investigation was to evaluate the subsurface conditions at the site and provide geotechnical recommendations for the proposed security improvements. We performed the following scope of services:

- Performed a site reconnaissance to observe current site conditions.
- Notified subscribing utility companies via Underground Service Alert (USA) a minimum of two working days (as required by law) prior to performing exploratory excavations at the site.
- Performed two pavement cores (C1 and C2), one at each proposed improvement location, and measured the existing pavement section thickness. Approximate core locations are shown on the Site Plan, Figure 2.
- Performed two dynamic cone penetrometer (DCP) soundings (DCP1 and DCP2), one at each core location, to measure in-situ soil consistency and relative density to refusal depths of approximately two to three feet.
- Obtained representative soil samples from the pavement cores using a hand-auger.
- Logged the borings in accordance with the Unified Soil Classification System (USCS).
- Upon completion, backfilled and patched the pavement cores with rapid-set concrete dyed black
- Performed laboratory test on the shallow soil samples to evaluate pertinent geotechnical parameters.
- Prepared this summary letter report with our findings, conclusions, and recommendations.

#### SITE AND PROJECT DESCRIPTION

The project site consists of the California Office of Emergency Services (OES) facility located at 3650 Schriever Avenue in Mather, California. The site includes three buildings with paved parking lots occupying much of the remaining land at the site. The existing security at the vehicular entrances to the site consists of barrier arms and a guard kiosk at one of the entrances. The site is relatively flat with elevations ranging between approximately 78 to 83 feet, as per the WGS84 EGM96 Geoid datum used by Google Earth.

The project consists of installing new security gates and guard kiosks at the two entrance and exits drives. The new security gates will likely consist of barrier arms secured to shallow foundations. The new guard kiosks will likely consist of a small ballistic rated structures supported on shallow concrete footings. The current site configuration, with proposed improvement areas outlined, is shown on the Site Plan, Figure 2.

#### SUBSURFACE CONDITIONS

Based on geologic mapping by the California Geological Survey (*Preliminary Geologic Map of the Sacramento 30'x60' Quadrangle, California*, Gutierrez, 2011.), the site is underlain by Riverbank Formation materials (map symbol Qr).

The subsurface conditions encountered in our explorations consisted of the following:

#### **Existing Pavement Section**

Pavement sections composing of hot-mix asphalt (HMA) constructed over aggregate base (AB) were observed at both proposed improvement locations. Pavement sections were measured to be 4½-inches HMA over 11½-inches AB and 3½-inches HMA over 11½-inches AB at locations C1/DCP1 and C2/DCP2 respectively.

#### **Riverbank Formation**

Below the structural pavement sections at both core locations (C1/DCP1 and C2/DCP2) we encountered Riverbank Formation consisting of very stiff to hard, moist, reddish brown sandy lean clay with gravel (CL) to the maximum depth explored of approximately three feet. Each DCP and hand-auger boring attempt was met with shallow refusal.

The soil conditions described herein are generalized. The attached Key to Logs and Boring Logs HA1 through HA2 (Figures 3 through 5) detail soil type, color, moisture, consistency, and classification of the soil encountered at specific locations and elevations. The attached DCP logs (Figures 6 and 7) detail relative soil in-situ soil consistency and relative density.

#### Groundwater

We did not encounter static groundwater in our explorations advanced to a maximum depth of approximately three feet on July 26, 2022.

We reviewed available depth-to-groundwater data on the California Department of Water Resources (DWR) Sustainable Groundwater Management Act (SGMA) Application (https://sgma.water.ca.gov/webgis/).

The SGMA website indicates that the average depth to groundwater in the site vicinity is approximately 80 feet (Spring & Fall 2021).

It should be noted that fluctuations in the level of groundwater may occur due to variations in rainfall, temperature, and other factors. Depth to groundwater can also vary significantly due to localized pumping, irrigation practices, and seasonal fluctuations. Therefore, it is possible that groundwater may be higher or lower than the level observed during our investigation.

#### **Laboratory Test Results**

Laboratory tests were performed in accordance with generally accepted test methods of the American Society for Testing and Materials (ASTM) or other suggested procedures. Selected soil samples were tested for their plasticity characteristics, corrosion potential, and resistance values.

We performed pH, resistivity, chloride, and sulfate tests on a representative near-surface sample to generally evaluate the corrosion potential of the soil with respect to proposed subsurface structures. These tests were performed in accordance with California Test Method (CTM) Nos. 643, 422, and 417. The results are presented in Table 1 and should be considered for design of underground structures.

TABLE 1 SOIL CORROSION PARAMETER TEST RESULTS (CALIFORNIA TEST METHODS 643, 417, AND 422)

Sample No.	Sample Depth (ft.)	pН	Minimum Resistivity (ohm-cm)	Chloride (ppm)	Sulfate (ppm)
Combo Bulk	1.25-3	6.37	5,090	2.2	22.3

Soil with a low pH (higher acidity) is considered corrosive as it can react with lime in cement to leach out soluble reaction products and result in a more porous and weaker concrete. Per Caltrans *Corrosion Guidelines* (Caltrans 2021), soil with a pH of 5.5 or lower may be corrosive to concrete or steel in contact with the ground.

Soil resistivity is the measure of the soil's ability to transmit electric current. Corrosion of buried ferrous metal is proportional to the resistivity of the soil. A lower resistivity indicates a higher propensity for transmitting electric currents that can cause corrosion of buried ferrous metal items. In general, the higher the resistivity, the lower the rate for corrosion. Per Caltrans *Corrosion Guidelines* (Caltrans 2021), resistivity serves as an indicator parameter for the possible presence of soluble salts and it is not included as a parameter to define a corrosive area for structures. A minimum resistivity value for soil less than 1,500 ohm-cm may indicate the presence of high quantities of soluble salts and a higher propensity for corrosion.

Table 2 presents a summary of concrete requirements set forth by the California Builders Code (CBC) Section 1904 (CBC 2016 Vol 1 & 2) and American Concrete Institute (ACI) 318 for possible chloride exposure. Chlorides can break down the protective oxide layer on steel surfaces resulting in corrosion. Sources of chloride include, but are not limited to, deicing chemicals, salt, brackish water, seawater, or spray from these sources.

## TABLE 2 REQUIREMENTS FOR CONCRETE EXPOSED TO CHLORIDE-CONTAINING SOLUTIONS (AFTER ACI 318 TABLES 19.3.1.1 and 19.3.2.1)

Chloride Severity	Exposure Class	Condition	Maximum Water to Cement Ratio by Weight	Minimum Compressive Strength (psi)
Not Applicable	C0	Concrete dry or protected from moisture	N/A	2,500
Moderate	C1	Concrete exposed to moisture but not to external sources of chlorides	N/A	2,500
Severe	C2	Concrete exposed to moisture and an external source of chlorides	0.40	5,000

The appropriate Chloride Severity/Exposure Class should be determined by the project designer based on the specific conditions at the location of the proposed structure. Further guidance is provided in ACI 318. Per Caltrans *Corrosion Guidelines*, soil with a chloride concentration of 500 ppm or higher may be corrosive to steel structures or steel reinforcement in concrete. Based on Caltrans criteria, soil at the locations tested is not corrosive with respect to chloride content.

Table 3 presents a summary of concrete requirements set forth by CBC Section 1904 and ACI 318 for sulfate exposure. Similar to chlorides, sulfates can break down the protective oxide layer on steel leading to corrosion. Sulfates can also react with lime in cement to soften and crack concrete.

## TABLE 3 REQUIREMENTS FOR CONCRETE EXPOSED TO SULFATE-CONTAINING SOLUTIONS (AFTER ACI 318 TABLES 19.3.1.1 and 19.3.2.1)

			oluble Sulfate 4) Content	Cement	Maximum Water to	Minimum
Sulfate Severity	Exposure Class	Percent By Mass	Parts Per Million (ppm)	Type (ASTM C 150)	Cement Ratio by Weight1	Compressive Strength (psi)
Not Applicable	S0	SO4 < 0.10	SO4 < 1,000	No Type Restriction	N/A	2,500
Moderate	S1	0.10 < SO4 < 0.20	1,000 < SO4 < 2,000	II	0.50	4,000
Severe	S2	0.20 < SO4 < 2.00	2,000 < SO4 < 20,000	V	0.45	4,500
Very Severe	S3	SO4 > 2.00	SO4 > 20,000	V+Pozzolan or Slag	0.45	4,500

#### **Notes:**

1. Maximum water to cement ratio limits are different for lightweight concrete, see ACI 318 for details.

Based on the laboratory test results, the Sulfate Severity is classified as "Not Applicable", and the Exposure Class is S0. The concrete mix design(s) should be developed accordingly. The presence of water-soluble sulfates is not a visually discernible characteristic; therefore, other soil samples from the site could yield different concentrations. Additionally, over time landscaping activities (i.e., addition of fertilizers and other soil nutrients) may affect the concentration.

Geocon does not practice in the field of corrosion engineering and the above information is provided as screening criteria only. If corrosion sensitive improvements are planned, we recommend that further evaluations by a corrosion engineer be performed to incorporate the necessary precautions to avoid premature corrosion on buried metal pipes and metal or concrete structures in direct contact with the soils.

We performed a laboratory R-Value test on a representative near-surface sample. The R-Value test results are summarized in Table 4

## TABLE 4 R-VALUE TEST RESULTS ASTM D2844

Sample Number	Depth (feet)	(mof)		R-Value
Combo Bulk	1.25-3	132.8	8.9	12

We performed a laboratory Plasticity Index test on a representative near-surface sample which indicate medium plasticity. Plasticity Index test results are attached as Figure 8.

#### **Geologic Hazards**

Based on the subsurface conditions encountered during this investigation, geologically-mapped subgrade materials, and our experience in the project area, the site is not subject to significant geologic hazards including active faulting, liquefaction, lateral spreading/dynamic stability, or expansive soil.

#### **CONCLUSIONS AND RECOMMENDATIONS**

#### General

No soil or geologic conditions have been identified that would preclude the proposed security improvement construction as presently planned, provided the recommendations contained in this limited geotechnical report are incorporated into design and construction of the project.

#### Seismic Site Class / Seismic Design Criteria

We understand that seismic design of the proposed new foundation will be performed in accordance with the provisions of the 2019 CBC, the seismic provisions of which are based on the American Society of Civil Engineers (ASCE)/Structural Engineering Institute (SEI) publication: *ASCE/SEI 7-16, Minimum Design Loads and Associated Criteria for Buildings and Other Structures* (ASCE/SEI, 2017). We used the Structural Engineers Association of California (SEAOC) and Office of Statewide Health Planning and Development (OSHPD) web application *Seismic Design Maps* (https://seismicmaps.org/) to evaluate code-based seismic design parameters in accordance with ASCE 7-16.

For seismic design purposes, sites are classified as Site Class "A" through "F" as follows:

- Site Class A Hard Rock;
- Site Class B Rock;
- Site Class C Very Dense Soil and Soft Rock;
- Site Class D Stiff Soil;
- Site Class E Soft Clay Soil; and
- Site Class F Soils Requiring Site Response Analysis.

Based on the subsurface conditions at the site, the conservative Site Classification is a Site Class "D" per Table 20.3-1 of ASCE/SEI 7-16. For the purposes of evaluating code-based seismic parameters for design, we assume a seismic Risk Category II (per the CBC) for the project. Results are summarized in Table 5.

TABLE 5
ASCE 7-16 (CODE-BASED) SEISMIC DESIGN PARAMETERS
SITE CLASS "D" – STIFF SOIL

Parameter	Value	ASCE 7-16 Reference
MCE <sub>R</sub> Ground Motion Spectral Response Acceleration – Class B (short), <b>S</b> s	0.464g	Figure 22-1
MCE <sub>R</sub> Ground Motion Spectral Response Acceleration – Class B (1 sec), S <sub>1</sub>	0.226g	Figure 22-2
Site Coefficient, FA	1.429	Table 11.4-1
Site Coefficient, Fv	2.148*	Table 11.4-2
Site Class Modified MCE <sub>R</sub> Spectral Response Acceleration (short), S <sub>MS</sub>	0.663g	Eq. 11.4-1
Site Class Modified MCE <sub>R</sub> Spectral Response Acceleration (1 sec), S <sub>M1</sub>	0.728g*	Eq. 11.4-2
5% Damped Design Spectral Response Acceleration (short), S <sub>DS</sub>	0.442g	Eq. 11.4-3
5% Damped Design Spectral Response Acceleration (1 sec), S <sub>D1</sub>	0.485g*	Eq. 11.4-4

<sup>\*</sup> Per Supplement 3 of ASCE7-16 (effective November 5, 2021), a ground motion hazard analysis (GMHA) shall be performed for projects on Site Class "D" sites with 1-second spectral acceleration (S1) greater than or equal to 0.2g, which is true for this site. However, Supplement 3 of ASCE 7-16 provides an exception stating that that the GMHA may be waived provided that the parameter SM1 is increased by 50% for all applications of SM1. The values for parameters SM1 and SD1 presented above have been increased in accordance with Supplement 3 of ASCE 7-16.

Table 6 presents the mapped maximum considered geometric mean (MCE<sub>G</sub>) seismic design parameters for projects located in Seismic Design Categories of D through F, in accordance with ASCE 7-16.

TABLE 6
ASCE 7-16 PEAK GROUND ACCELERATION PARAMETERS

Parameter	Value	ASCE 7-16 Reference
Mapped MCE <sub>G</sub> Peak Ground Acceleration, PGA	0.195g	Figure 22-7
Site Coefficient, F <sub>PGA</sub>	1.409	Table 11.8-1
Site Class Modified MCEG Peak Ground Acceleration, PGA <sub>M</sub>	0.275g	Section 11.8.3 (Eq. 11.8-1)

Conformance to the criteria presented in Tables 5 and 6 for seismic design does not constitute any kind of guarantee or assurance that significant structural damage or ground failure will not occur if a maximum level earthquake occurs. The primary goal of seismic design is to protect life and not to avoid structural damage, as such design may be economically prohibitive.

#### **Soil Excavation Characteristics**

Grading and excavations at the site may be accomplished with standard effort using heavy-duty grading/excavation equipment. Project excavations may generate some oversized rock material (greater than 6 inches in max dimension) or boulders.

Temporary excavations must meet Cal/OSHA requirements as appropriate. Excavation sloping, benching, the use of trench shields, and the placement of trench spoils should conform to the latest applicable Cal/OSHA standards. The contractor should have a Cal/OSHA-approved "competent person" onsite during excavation to evaluate trench conditions and to make appropriate recommendations where necessary. It is the contractor's responsibility to provide sufficient and safe excavation support, as well as to protect nearby utilities, structures, and other improvements that may be damaged by earth movements.

The excavation support recommendations provided by Cal/OSHA are generally geared toward protecting human life and not necessarily toward preventing damage to nearby structures or surface improvements. The contractor should be responsible for using the proper active shoring systems or sloping to prevent damage to any structure or improvements near underground excavations.

If grading occurs during or after the wet season (typically winter and spring), or in periods of precipitation, in-place and excavated soils will likely be wet. In addition, landscape irrigation practices at the site may cause wet soil conditions any time of the year. Earthwork contractors should be aware of moisture sensitivity of clayey and fine-grained soils and potential compaction/workability difficulties.

Earthwork and pad preparation operations in these conditions will likely be difficult with low productivity. Often, a period of at least one month of warm and dry weather is necessary to allow the site to dry sufficiently so that heavy grading equipment can operate effectively. Conversely, during dry summer and fall months, dry clay soils may require additional grading effort (discing, mixing, or other means) to attain proper moisture conditioning.

Due to the fine-grained nature of the soils, additional drying efforts to attain moisture contents suitable for compaction should be anticipated regardless of the time of year. Mitigation alternatives may include aerating/drying the exposed soils (assuming favorable weather conditions), or chemical treatment (e.g., lime treatment). Unstable excavation bottoms may require over-excavating 12 to 18 inches and placing geotextile fabric/geogrid covered with aggregate, for stabilization. We can provide specific recommendations during construction, based on conditions encountered.

- 7 -

#### **Materials for Fill**

Excavated soils generated from cut operations at the site are suitable for use as fill in structural areas, provided they do not contain deleterious matter, organic material, or cementations larger than 6 inches in maximum dimension. Native soils reused as engineered fill may require aerating/drying to attain suitable moisture content for compaction, regardless of the time of year.

Import fill material should be primarily granular with a "low" expansion potential (Expansion Index less than 50), a Plasticity Index less than 15, be free of organic material and construction debris, and not contain rock/cementations larger than 6 inches in greatest dimension.

Environmental characteristics and corrosion potential of import soil materials should also be considered. Proposed import materials should be sampled, tested, and approved by Geocon prior to its transportation to the site.

#### Grading

All earthwork operations should be observed and all fills tested for recommended compaction and moisture content by a representative of Geocon.

All references to relative compaction and optimum moisture content in this report are based on the latest ASTM D1557 Test Procedure. Structural areas should be considered the areas extending a minimum of 5 feet beyond the outside dimensions of structures, including footings or overhangs carrying structural loads.

Within areas to be developed, any existing structures, underground utilities, debris, organic matter and organic rich topsoil should be removed. Roots larger than 1 inch in diameter should be completely removed. Smaller roots may be left in place as conditions warrant and at the discretion of our field representative.

After site preparation, the entire footprints of the proposed new barrier arms and guard kiosks (structure footprints plus a 5-foot overbuild) should be excavated to firm native soil, anticipated to be approximately 1½ to 2 feet below existing pavement surface.

The bottom of the excavation should be scarified 12 inches, uniformly moisture-conditioned at or above optimum moisture content, and compacted to at least 90% relative compaction. Scarification and recompaction operations should be performed in the presence of a Geocon representative to evaluate performance of the subgrade under compaction equipment loading and to identify any loose or unstable soil conditions that could require additional excavation.

Engineered fill should be placed and compacted in horizontal lifts not exceeding 8 inches (loose thickness) and brought to final subgrade elevations. Each lift should be moisture-conditioned at or above optimum and compacted to at least 90% relative compaction.

Underground utility trenches within structural areas should be backfilled with properly compacted material. Pipe bedding, shading, and trench backfill should conform to the requirements of the appropriate utility authority. Material excavated from trenches should be adequate for use as general backfill above shading, provided it does not contain deleterious matter, vegetation, or cementations larger than 6 inches in maximum dimension. Trench backfill should be placed in loose lifts not exceeding 8 inches, moisture-conditioned at or above optimum, and compacted to at least 90% relative compaction. Compaction should be performed by mechanical means only; jetting of trench backfill is not recommended.

- 8 -

#### **Foundation Design Criteria**

The new foundations for the barrier arms and guard kiosks may consist of conventional shallow foundations bearing on undisturbed native soil.

Foundations may consist of strip footings, isolated spread footings, or combinations thereof. Strip footings should be at least 12 inches wide, and spread footings should be at least 18 inches square. All footings should extend a minimum of 12 inches below lowest adjacent grade and bear within undisturbed native soil. Any soft or disturbed native soil should be removed and replaced with engineered fill.

Underground utilities running parallel to footings should not be constructed in the zone of influence of footings. The zone of influence may be taken to be the area within 18 inches (laterally) of the footing, beneath the footing, and within a 1:1 plane extending out and down from the bottom of the footing.

Shallow foundations proportioned as recommended above may be designed for an allowable soil bearing capacity of 2,000 pounds per square foot (psf) for dead plus live loads. A one-third increase in allowable bearing capacity is permitted for use with the alternative load combinations given in Section 1605.3.2 of the CBC.

The allowable passive pressure used to resist lateral movement of the footings may be assumed to be equal to a fluid weighing 350 pounds per cubic foot (pcf). The allowable coefficient of friction to resist sliding is 0.35 for concrete against soil. Combined passive resistance and friction may be utilized for design provided that the passive resistance is reduced by 50%.

Continuous footings should be reinforced with at least two No. 4 reinforcing bars, one placed near the top and one placed near the bottom to provide structural continuity and span local soil irregularities. The project structural engineer should determine the need for additional reinforcement based on structural requirements. Reinforcement for spread footings should be determined by the project structural engineer.

A Geocon representative should observe foundation excavations prior to placing reinforcing steel or concrete to observe that the exposed soil conditions are consistent with those anticipated. If unanticipated soil conditions are encountered, foundation modifications may be required.

#### **Pavement – Hot Mix Asphalt**

We performed Resistance-Value (R-Value) testing on one representative composite bulk soil sample. Our testing resulted in an R-Value of 12. To account for subgrade soil variability and based on our experience in the area, we recommend using an R-Value of 10 for the purpose of pavement design.

We recommend the following alternative hot mix asphalt (HMA) pavement sections for design. The project civil engineer should determine the appropriate Traffic Index (TI) based on anticipated traffic conditions. Table 5 provides alternative pavement sections based on assumed TIs. We can provide additional sections based on other TIs if necessary.

TABLE 5
FLEXIBLE PAVEMENT SECTIONS

Pavement Area	nt Area Design TI HMA <sup>1</sup> (inches)		AB <sup>2</sup> (inches)	
Automobile Parking Areas	5.0	3.0	9.0	
Driveways / Truck Areas	6.5	4.0	13.0	

#### Notes:

- 1. HMA = Hot Mix Asphalt (Type A) conforming to Section 39 of Caltrans' latest Standard Specifications.
- 2. AB = Class 2 Aggregate Base conforming to Section 26 of Caltrans' latest Standard Specifications.

The recommended pavement sections are based on the following assumptions:

- 1. Subgrade soil has a minimum R-Value of 10.
- 2. Subgrade soil is stable, moisture-conditioned, and compacted in accordance with the recommendations of this report. Prior to placing AB, subgrade soil should be proof rolled with a loaded water truck to verify stability.
- 3. Class 2 AB has a minimum R-Value of 78 and meets the requirements of Section 26 of the latest Caltrans Standard Specifications.
- 4. Class 2 AB and the top 6 inches of subgrade are compacted to 95% or higher relative compaction at or near optimum moisture content. Prior to placing AC, the AB should be proof-rolled with a loaded water truck to verify stability.
- 5. HMA should conform to Section 39 of Caltrans' latest Standard Specifications.
- 6. Periodic maintenance of HMA pavements is performed.

HMA pavement section recommendations for driveways and parking areas are based on the design procedures of Caltrans' Highway Design Manual (Design Manual), Chapter 600, latest edition. It should be noted that most rational pavement design procedures are based on projected street or highway traffic conditions and, hence, may not be representative of vehicular loading that occurs in parking lots and driveways. Pavement proximity to landscape irrigation, reduced traffic speed and short turning radii increase the potential for pavement distress to occur in parking lots even though the volume of traffic is significantly less than that of an adjacent street. The Design Manual indicates that the resulting pavement sections for parking lots are "minimized to keep initial costs down but are reasonable because additional HMA surfacing can be added later, if needed, and generally without incurring traffic hazards or traffic handling problems." It is generally not economically feasible to design and construct the entire parking lot and driveways for the unique loading conditions previously described. Periodic maintenance of the pavement in these areas, therefore, should be anticipated.

To reduce the potential for water from landscaped areas migrating under pavement into the AB, consideration should be given to using full-depth curbs in areas where pavement abuts irrigated landscaping. The full-depth curbs should extend at least 4 inches or more into the soil subgrade beneath the AB. Alternatively, modified drop-inlets that contain weep-holes may be used to encourage accumulated water to drain from beneath the pavement.

- 10 -

#### Pavement - Rigid Concrete

If rigid Portland cement concrete (PCC) pavement is used in automobile and light-truck traffic areas, we recommend that the PCC pavement be at least 6 inches thick. PCC pavement should be underlain by at least 6 inches of Class 2 AB meeting the requirements of Section 26 of Caltrans' Standard Specifications and compacted to at least 95% relative compaction.

The upper 6 inches of subgrade soils should be prepared and compacted to a minimum of 95 percent relative compaction in accordance with the recommendations of this report. Subgrade should be finished to a smooth, unyielding surface and proof-rolled with a loaded water truck to verify stability.

PCC should have a minimum 28-day compressive strength of 3,500 pounds per square inch (psi). Adequate construction and crack control joints should be used to control cracking inherent in concrete construction. It would be advantageous to provide minimal reinforcement, such as No. 3 steel bars placed 18 inches on center in both horizontal directions to help control cracking. We note that the American Concrete Pavement Association (ACPA) recommends a maximum joint spacing no greater than 24X the slab thickness for PCC pavements directly underlain by granular bases.

Adequate dowels should also be used at joints to facilitate load transfer and reduce vertical offset. To reduce the potential for water from landscaped areas migrating under pavement into the AB, consideration should be given to using full-depth curbs in areas where pavement abuts irrigated landscaping. The full-depth curbs should extend at least 4 inches or more into the soil subgrade beneath the AB. Alternatively, modified drop-inlets that contain weep-holes may be used to encourage accumulated water to drain from beneath the pavement.

In general, we recommend that concrete pavements be detailed, designed, constructed, and maintained in accordance with industry standards such as those provided by the ACI and ACPA.

#### LIMITATIONS

The recommendations of this report pertain only to the site investigated and are based upon the assumption that the soil conditions do not deviate from those disclosed in the investigation. If any variations or undesirable conditions are encountered during construction, or if the proposed construction will differ from that anticipated herein, we should be notified so that supplemental recommendations can be given. The evaluation or identification of the potential presence of hazardous materials or environmental contamination was not part of our scope of services.

This report is issued with the understanding that it is the responsibility of the owner or their representative to ensure that the information and recommendations contained herein are brought to the attention of the design team for the project and incorporated into the plans and specifications, and the necessary steps are taken to see that the contractor and subcontractors carry out such recommendations in the field. The recommendations contained in this report are preliminary until verified during construction by representatives of our firm. Changes in the conditions of a property can occur with the passage of time, whether they are due to natural processes or the works of man on this or adjacent properties. Additionally, changes in applicable or appropriate standards may occur, whether they result from legislation or the broadening of knowledge. Accordingly, the findings of this report may be invalidated partially or wholly by changes outside our control. Therefore, this report is subject to review and should not be relied upon after a period of three years.

The firm that performed the geotechnical investigation for the project, the Geotechnical Engineer of Record (GER), should be retained to provide testing and observation services during construction to provide continuity of geotechnical interpretation and to verify that the recommendations presented for geotechnical aspects of site development are incorporated during site grading, construction of improvements, and excavation of foundations. If another geotechnical firm is selected to perform the testing and observation services during construction operations, that firm should prepare a letter indicating their intent to assume the responsibilities of the GER and either acknowledgement of their concurrence with the recommendations presented in our report or revised recommendations based on their own analyses.

Our professional services were performed, our findings obtained, and our recommendations prepared in accordance with generally accepted geotechnical engineering principles and practices used in the site area at this time. No warranty is provided, either express or implied.

Please contact us if you have any questions concerning the contents of this report or if we may be of further service.

Sincerely,

GEOCON CONSULTANTS, INC.

Ronald E. Loutzenhiser, PE, GE

Senior Engineer

Jeremy Zorne, PE

Senior Engineer/Vice President


Attachments: Figure 1, Vicinity Map


Figure 2, Site Plan Figure 3, Key to Logs

Figures 4 and 5, Boring Logs (C1/DCP1 and C2/DCP2)

Figures 6 and 7, Dynamic Cone Penetrometer Logs (C1/DCP1 and C2/DCP2)

Figure 8, Plasticity Index Test Results





#### UNIFIED SOIL CLASSIFICATION **MAJOR DIVISIONS TYPICAL NAMES** WELL GRADED GRAVELS WITH OR WITHOUT SAND, LITTLE OR NO FINES D GW CLEAN GRAVELS WITH LITTLE OR NO FINES POORLY GRADED GRAVELS WITH OR WITHOUT SAND, LITTLE OR NO FINES GRAVELS GP MORE THAN HALF COARSE FRACTION IS LARGER THAN NO.4 SIEVE SIZE Ь SILTY GRAVELS, SILTY GRAVELS WITH MORE THAN HALF IS COARSER THAN NO. 200 SIEVE GM COARSE-GRAINED SOILS GRAVELS WITH OVER 12% FINES CLAYEY GRAVELS, CLAYEY GRAVELS WITH SAND GC WELL GRADED SANDS WITH OR SW WITHOUT GRAVEL, LITTLE OR NO FINES CLEAN SANDS WITH LITTLE OR NO FINES POORLY GRADED SANDS WITH OR WITHOUT GRAVEL, LITTLE OR NO FINES SANDS SP MORE THAN HALF COARSE FRACTION IS SILTY SANDS WITH OR WITHOUT GRAVEL SMALLER THAN NO.4 SM SIEVE SIZE SANDS WITH OVER 12% FINES CLAYEY SANDS WITH OR WITHOUT SC INORGANIC SILTS AND VERY FINE ML SANDS, ROCK FLOUR, SILTS WITH SANDS AND GRAVELS INORGANIC CLAYS OF LOW TO MEDIUM SILTS AND CLAYS FINE-GRAINED SOILS MORE THAN HALF IS FINER THAN NO. 200 SIEVE PLASTICITY, CLAYS WITH SANDS AND GRAVELS, LEAN CLAYS CL LIQUID LIMIT 50% OR LESS ORGANIC SILTS OR CLAYS OF LOW OL INORGANIC SILTS, MICACEOUS OR MH DIATOMACEOUS, FINE SANDY OR SILTY SOILS, ELASTIC SILTS INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS SILTS AND CLAYS СН LIQUID LIMIT GREATER THAN 50% ORGANIC CLAYS OR CLAYS OF MEDIUM ОН TO HIGH PLASTICITY

#### BORING/TRENCH LOG LEGEND

PT 4 14

HIGHLY ORGANIC SOILS

PEAT AND OTHER HIGHLY ORGANIC

-No Recovery	PENETRATION RESISTANCE					CE	
	SAN	D AND GRA	VEL	SILT AND CLAY			
Shelby Tube Sample	RELATIVE DENSITY	BLOWS PER FOOT (SPT)*	BLOWS PER FOOT (MOD-CAL)*	CONSISTENCY	BLOWS PER FOOT (SPT)*	BLOWS PER FOOT (MOD-CAL)*	COMPRESSIVE STRENGTH (tsf)
- Bulk Sample	VERY LOOSE	0 - 4	0-6	VERY SOFT	0 - 2	0 - 3	0 - 0.25
<u> </u> ∞	LOOSE	5 - 10	7 - 16	SOFT	3 - 4	4 - 6	0.25 - 0.50
— SPT Sample	MED <b>I</b> UM DENSE	11 - 30	17 - 48	MEDIUM STIFF	5 <b>-</b> 8	7 - 13	0.50 - 1.0
- Modified California Sample	DENSE	31 - 50	49 - 79	STIFF	9 - 15	14 - 24	1.0 - 2.0
▼—Groundwater Level	VERY DENSE	OVER 50	OVER 79	VERY STIFF	16 - 30	25 - 48	2.0 - 4.0
(At Completion)				HARD	OVER 30	OVER 48	OVER 4.0
☐ Groundwater Level     (Seepage)				IER FALLING 30 AN 18-INCH DR			

#### **MOISTURE DESCRIPTIONS**

FIELD TEST	APPROX. DEGREE OF SATURATION, S (%)	DESCRIPTION
NO INDICATION OF MOISTURE; DRY TO THE TOUCH	S<25	DRY
SLIGHT INDICATION OF MOISTURE	25 <u>&lt;</u> S<50	DAMP
INDICATION OF MOISTURE; NO VISIBLE WATER	50 <u>&lt;</u> S<75	MOIST
MINOR VISIBLE FREE WATER	75 <u>&lt;</u> S<100	WET
VISIBLE FREE WATER	100	SATURATED

#### **QUANTITY DESCRIPTIONS**

APPROX. ESTIMATED PERCENT	DESCRIPTION
<5%	TRACE
5 - 10%	FEW
11 - 25%	LITTLE
26 - 50%	SOME
>50%	MOSTLY

#### **GRAVEL/COBBLE/BOULDER DESCRIPTIONS**

	CRITERIA	DESCRIPTION
ı	PASS THROUGH A 3-INCH SIEVE AND BE RETAINED ON A NO. 4 SIEVE (#4 TO 3")	GRAVEL
ı	PASS A 12-INCH SQUARE OPENING AND BE RETAINED ON A 3-INCH SIEVE (3"-12")	COBBLE
ı	WILL NOT PASS A 12-INCH SQUARE OPENING (>12")	BOULDER

#### **LABORATORY TEST KEY**

CP - COMPACTION CURVE (ASTM D1557)

CR - CORROSION ANALYSIS (CTM 422, 643, 417)

DS - DIRECT SHEAR (ASTM D3080)

EI - EXPANSION INDEX (ASTM D4829) GSA - GRAIN SIZE ANALYSIS (ASTM D422)

MC - MOISTURE CONTENT (ASTM D2216) PI - PLASTICITY INDEX (ASTM D4318)

R - R-VALUE (CTM 301)

SE - SAND EQUIVALENT (CTM 217)

TXCU - CONSOLIDATED UNDRAINED TRIAXIAL (ASTM D4767)

TXUU – UNCONSOLIDATED UNDRAINED TRIAXIAL (ASTM D2850)

UC – UNCONFINED COMPRESSIVE STRENGTH (ASTM D2166)

#### **BEDDING SPACING DESCRIPTIONS**

THICKNESS/SPACING	DESCRIPTOR
GREATER THAN 10 FEET	MASSIVE
3 TO 10 FEET	VERY THICKLY BEDDED
1 TO 3 FEET	THICKLY BEDDED
3 <b>%-I</b> NCH TO 1 FOOT	MODERATELY BEDDED
1 <b>¼-I</b> NCH TO 3 <b>%-I</b> NCH	THINLY BEDDED
%-INCH TO 1 ¼-INCH	VERY THINLY BEDDED
LESS THAN %-INCH	LAMINATED

#### STRUCTURE DESCRIPTIONS

CRITERIA	DESCRIPTION
ALTERNATING LAYERS OF VARYING MATERIAL OR COLOR WITH LAYERS AT LEAST  N-INCH THICK	STRATIFIED
ALTERNATING LAYERS OF VARYING MATERIAL OR COLOR WITH LAYERS LESS THAN  N-INCH THICK	LAMINATED
BREAKS ALONG DEFINITE PLANES OF FRACTURE WITH LITTLE RESISTANCE TO FRACTURING	FISSURED
FRACTURE PLANES APPEAR POLISHED OR GLOSSY, SOMETIMES STRIATED	SLICKENSIDED
COHESIVE SOIL THAT CAN BE BROKEN DOWN INTO SMALLER ANGULAR LUMPS WHICH RESIST FURTHER BREAKDOWN	BLOCKY
INCLUSION OF SMALL POCKETS OF DIFFERENT SOIL, SUCH AS SMALL LENSES OF SAND SCATTERED THROUGH A MASS OF CLAY	LENSED
SAME COLOR AND MATERIAL THROUGHOUT	HOMOGENOUS

#### CEMENTATION/INDURATION DESCRIPTIONS

FIELD TEST	DESCRIPTION
CRUMBLES OR BREAKS WITH HANDLING OR LITTLE FINGER PRESSURE	WEAKLY CEMENTED/INDURATED
CRUMBLES OR BREAKS WITH CONSIDERABLE FINGER PRESSURE	MODERATELY CEMENTED/INDURATED
WILL NOT CRUMBLE OR BREAK WITH FINGER PRESSURE	STRONGLY CEMENTED/INDURATED

#### IGNEOUS/METAMORPHIC ROCK STRENGTH DESCRIPTIONS

FIELD TEST	DESCRIPTION
MATERIAL CRUMBLES WITH BARE HAND	WEAK
MATERIAL CRUMBLES UNDER BLOWS FROM GEOLOGY HAMMER	MODERATELY WEAK
%-INCH INDENTATIONS WITH SHARP END FROM GEOLOGY HAMMER	MODERATELY STRONG
HAND-HELD SPECIMEN CAN BE BROKEN WITH <b>ONE</b> BLOW FROM GEOLOGY HAMMER	STRONG
HAND-HELD SPECIMEN CAN BE BROKEN WITH COUPLE BLOWS FROM GEOLOGY HAMMER	VERY STRONG
HAND-HELD SPECIMEN CAN BE BROKEN WITH <b>MANY</b> BLOWS FROM GEOLOGY HAMMER	EXTREMELY STRONG

#### IGNEOUS/METAMORPHIC ROCK WEATHERING DESCRIPTIONS

DEGREE OF DECOMPOSITION	FIELD RECOGNITION	ENGINEERING PROPERTIES
SOIL	DISCOLORED, CHANGED TO SOIL, FABRIC DESTROYED	EASY TO DIG
COMPLETELY WEATHERED	DISCOLORED, CHANGED TO SOIL, FABRIC MAINLY PRESERVED	EXCAVATED BY HAND OR RIPPING (Saprolite)
HIGHLY WEATHERED	DISCOLORED, HIGHLY FRACTURED, FABRIC ALTERED AROUND FRACTURES	EXCAVATED BY HAND OR RIPPING, WITH SLIGHT DIFFICULTY
MODERATELY WEATHERED	DISCOLORED, FRACTURES, INTACT ROCK-NOTICEABLY WEAKER THAN FRESH ROCK	EXCAVATED WITH DIFFICULTY WITHOUT EXPLOSIVES
SLIGHTLY WEATHERED	MAY BE DISCOLORED, SOME FRACTURES, INTACT ROCK-NOT NOTICEABLY WEAKER THAN FRESH ROCK	REQUIRES EXPLOSIVES FOR EXCAVATION, WITH PERMEABLE JOINTS AND FRACTURES
FRESH	NO DISCOLORATION, OR LOSS OF STRENGTH	REQUIRES EXPLOSIVES

#### IGNEOUS/METAMORPHIC ROCK JOINT/FRACTURE DESCRIPTIONS

FIELD TEST	DESCRIPTION
NO OBSERVED FRACTURES	UNFRACTURED/UNJOINTED
MAJORITY OF JOINTS/FRACTURES SPACED AT 1 TO 3 FOOT INTERVALS	SLIGHTLY FRACTURED/JOINTED
MAJORITY OF JOINTS/FRACTURES SPACED AT 4-INCH TO 1 FOOT INTERVALS	MODERATELY FRACTURED/JOINTED
MAJORITY OF JOINTS/FRACTURES SPACED AT 1-INCH TO 4-INCH INTERVALS WITH SCATTERED FRAGMENTED INTERVALS	INTENSELY FRACTURED/JOINTED
MAJORITY OF JOINTS/FRACTURES SPACED AT LESS THAN 1-INCH INTERVALS; MOSTLY RECOVERED AS CHIPS AND FRAGMENTS	VERY INTENSELY FRACTURED/JOINTED



3160 GOLD VALLEY DR - SUITE 800 - RANCHO CORDOVA, CA 95742 PHONE 916.852.9118 - FAX 916.852.9132

**KEY TO LOGS** 

Figure 3

DEPTH IN FEET	SAMPLE INTERVAL & RECOVERY	LITHOLOGY	GROUNDWATER	SOIL CLASS (USCS)	BORING C1/DCP1  ELEV. (MSL.)80' DATE COMPLETED	PENETRATION . RESISTANCE (BLOWS/FT.)	DRY DENSITY (P.C.F.)	MOISTURE CONTENT (%)	ADDITIONAL TESTS
- 0 -					MATERIAL DESCRIPTION				
Ů					ASPHALT - 4.25 Inches				
- 1 -	SG Combo				AGGREGATE BASE - 11.75 Inches	_			
- 2 -	X X X X X X X X X X X X X X X X X X X			CL	Very stiff to hard, moist, brown, Sandy Lean CLAY with Gravel				
, ,					PRACTICAL REFUSAL AT 3 FEET NO GROUNDWATER ENCOUNTERED BACKFILLED WITH SOIL CUTTINGS AND CAPPED WITH RAPID SET CONCRETE				

Figure 4, Log of Boring, page 1 of 1

IN PROGRESS S2120-05-08 CAL OES SECURITY.GPJ 09/13/22

		SAMPLING UNSUCCESSFUL	STANDARD PENETRATION TEST	DRIVE SAMPLE (UNDISTURBED)
GEOCON	SAMPLE SYMBOLS	DISTURBED OR BAG SAMPLE	CHUNK SAMPLE	▼ WATER TABLE OR SEEPAGE

DEPTH IN FEET	SAMPLE INTERVAL & RECOVERY	LITHOLOGY	GROUNDWATER	SOIL CLASS (USCS)	BORING C2/DCP2  ELEV. (MSL.)~81' DATE COMPLETED	PENETRATION . RESISTANCE (BLOWS/FT.)	DRY DENSITY (P.C.F.)	MOISTURE CONTENT (%)	ADDITIONAL TESTS
- 0 -					MATERIAL DESCRIPTION  ASPHALT - 3.5 Inches				
- 1 -					AGGREGATE BASE - 11.5 Inches				
	SG Combo √			CL	V 4'CC+ 1 - 1 - ' + - 11' 1 1 C- 1-1 - CI AV				
- 2 -	X X X X X	6/0/ 6/0/		CL	Very stiff to hard, moist, reddish brown, Sandy Lean CLAY with Gravel				
					PRACTICAL REFUSAL AT 2 FEET NO GROUNDWATER ENCOUNTERED BACKFILLED WITH SOIL CUTTINGS AND CAPPED WITH RAPID SET CONCRETE				

Figure 5, Log of Boring, page 1 of 1

IN PROGRESS S2120-05-08 CAL OES SECURITY.GPJ 09/13/22

	CAMPIE CVARDOLC	SAMPLING UNSUCCESSFUL	STANDARD PENETRATION TEST	DRIVE SAMPLE (UNDISTURBED)
GEOCON	SAMPLE SYMBOLS	DISTURBED OR BAG SAMPLE	CHUNK SAMPLE	▼ WATER TABLE OR SEEPAGE

10 sq. cm

Geocon Consultants, Inc.

LOCATION: Mather, California

PROJECT NUMBER: S2120-05-08
DATE STARTED: 07-26-2022
DATE COMPLETED: 07-26-2022

SURFACE ELEVATION: ~80

CONE AREA:

HOLE #: C1/DCP1
CREW: TH/JH
PROJECT: California Office of Emergency Services

WATER ON COMPLETION: N/A
ADDRESS: 3650 Schriever Avenue

HAMMER WEIGHT: 35 lbs.

	BLOWS	RESISTANCE	GRAPH OF CO	ONE RESISTANCE		TESTED CO	NSISTENCY
DEPTH	PER 10 cm	Kg/cm <sup>2</sup>	0 50	100 150	N'	SAND & SILT	CLAY
-	N/A					VERY LOOSE	VERY SOFT
-	N/A					VERY LOOSE	VERY SOFT
- 1 ft	N/A					VERY LOOSE	VERY SOFT
-	21	93.2	•••••	•••••	-	MEDIUM DENSE	VERY STIFF
-	24	106.6	•••••	•••••	-	MEDIUM DENSE	VERY STIFF
- 2 ft	14	62.2	•••••		17	MEDIUM DENSE	VERY STIFF
-	15	66.6	•••••	•	19	MEDIUM DENSE	VERY STIFF
-	28	124.3	•••••	••••••	-	DENSE	HARD
- 3 ft	45	199.8	•••••	••••••	-	VERY DENSE	HARD
- 1 m							
-							
- 4 ft							
-							
-							
- 5 ft							
-							
-							
- 6 ft	:						
-							
- 2 m							
- 7 ft							
=							
-							
- 8 ft	•						
-							
-							
- 9 ft							
-							
-							
- 3 m 10 ft							
-							
-							
-							
- 11 ft							
-							
10.0							
- 12 ft							
-							
- 12.0	. [						
- 4 m 13 ft	•						

Geocon Consultants, Inc.


PROJECT NUMBER: S2120-05-08 07-26-2022 DATE STARTED: DATE COMPLETED: 07-26-2022 SURFACE ELEVATION:

HOLE #: C2/DCP2

CREW: TH/JH PROJECT: California Office of Emergency Services N/A WATER ON COMPLETION: \_\_ ADDRESS: 3650 Schriever Avenue HAMMER WEIGHT: 35 lbs.

LOCATION: Mather, California CONE AREA: 10 sq. cm

BLOWS	SOFT SOFT SOFT SOFT RD
- N/A N/A N/A - 1 ft N/A - 32 142.1 - DENSE HAI - 2 ft - 2 ft 1 ft N/A - 2 ft - 2 ft 1 ft N/A - 1 ft N/A - 2 ft - 2 ft - 1 ft N/A - 1 f	SOFT SOFT RD
- 1 ft N/A 32 142.1 - DENSE HAF - 2 ft - 2 ft	SOFT RD
- 2 ft -	RD
- 2 ft -	
- 2 ft - 2 ft VERY DENSE HAI	
- 2 ft 	
2 8	
1- 3 H I I I I I I I	
- 1 m	
- 4 ft	
- 5 ft	
- 6 ft	
- 2 m	
- 7 ft	
- 8 ft	
-	
- 9 ft	
-	
- 3 m 10 ft	
-	
-	
-	
- 11 ft	
-	
-	
- 12 ft	
-	
-	
- 4 m 13 ft	



	Sample No.	Liquid Limit	Plastic Limit	Plasticity Index	% Pass #200 Sieve	Unified Soil Classification Description	Preparation Method
•	Combo Bulk	24	13	11		Lean Clay	dry



Geocon Consultants 3160 Gold Valley Drive, Suite 800 Rancho Cordova, CA 95742

## ATTERBERG LIMITS (ASTM D4318) Project: California Office of Emergency Services

Location: Sacramento, CA Number: S2120-05-08

Figure: 8 Date:

PI COPY 2 S2120-05-08 CAL OES SECURITY.GPJ US\_LAB.GDT 9/12/22

## LEGAL DESCRIPTION (PER PTR)

All that certain Real Property located in the County of Sacramento, State of California, described as follows:

Those portions of Lots 60, 61, 62, 65, 66 and 67, of Natomas American River Subdivision No. 4 as shown on the Amended Map thereof filed in the Office of the Recorder of the County of Sacramento in Book 15, Page 44 of Maps, described as

Beginning at a point on the Westerly line of said Lot 61 and the center line of Old Placerville Road, said point being the center line intersection of Old Placerville Road and Schriever Way; thence from said point of beginning along the Westerly line of said Lot 61 South 00° 45' 05" East, 462.69 feet; thence along the Westerly lines of said Lots 61 and 65 along the arc of a curve concave to the East and having a radius of 1432.69 feet and a central angle of 5° 48' 52" the chord of which bears South 3° 39' 31" East, 145.33 feet; thence leaving said Westerly line of said Lot 65 North 89° 15' 13" East, 316.39 feet; thence North 59°29' 40" East, 839.96 feet; thence North 30° 25' 42" West, 571.23 feet to a point on the center line of said Schriever Way; thence along said center line of said Schriever Way South 59° 29' 40" West 482.37 feet; thence continuing along said center line of said Schriever Way along the arc of a curve concave to the North and having a radius of 500 feet and a central angle of 29° 45' 33" the chord of which bears South 74° 22' 27" West, 256.79 feet; thence continuing along said center line of said Schriever Way South 89° 15' 13" West, 103.20 feet to the point of beginning of the herein described property.

Assessor's Parcel No: 077-0050-0-063-0000

### **COMMENTS**

UTILITIES ..

FLOOD ZONE .....

· SUBJECT PROPERTY LIES WITHIN FLOOD ZONE X (AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN) AS SHOWN ON FLOOD INSURANCE RATE MAP NUMBER 06067C0208H DATED AUGUST 16, 2012.

BASIS OF BEARINGS ..... THE BASIS OF BEARINGS FOR THIS SURVEY IS NAD 83, CALIFORNIA STATE COORDINATE SYSTEM, ZONE 2 (2017.5 EPOCH DATE) RESULTING IN THE CENTERLINE OF SCHRIEVER AVENUE BEING N59°29'19"E AND HAVING A RECORD BEARING OF N59°29'40"E AS SHOWN ON 56 RS 12. ALL DISTANCES AND COORDINATES CITED HEREIN ARE GROUND VALUES, WHICH ARE THE BASIS FOR THE AREAS SHOWN HEREON.

PARKING ... THERE CURRENTLY EXISTS A TOTAL OF 517 PARKING STALLS

WITHIN THE BOUNDARY, AS SHOWN HEREON.

OF THE TOTAL, 23 STALLS ARE DESIGNATED AS 'COMPACT', 4 STALLS ARE DESIGNATED AS 'CARPOOL', 3 STALLS ARE DESIGNATED AS 'COMPACT CARPOOL', 9 STALLS ARE DESIGNATED AS 'EV', 14 STALLS ARE DESIGNATED AS 'RESERVED', AND 18 STALLS ARE DESIGNATED AS 'HANDICAP'.

AREA ...... BASED UPON MEASURED BEARINGS AND DISTANCES AS SHOWN

HEREON, THE AREAS ARE:

586,894 SQ. FT. = 13.473 ACRES

544,115 SQ. FT. = 12.491 ACRES

PURPOSE OF SURVEY ..... THE PURPOSE OF THIS MAPPING IS TO CREATE AN ALTA DUE DILIGENCE SURVEY OF THE PROPERTY SHOWN AND LOCATED AT 3650 SCHRIEVER AVE, MATHER, CA. USING TABLE A ITEMS 2, 3, 4, 8, 9, 11, 13, AND 14 PER 2021 MINIMUM STANDARD DETAIL REQUIREMENTS FOR ALTA/NSPS LAND TITLE SURVEYS.

TABLE A, ITEM 14 ...... THE SUBJECT PROPERTY ABUTS OLD PLACERVILLE ROAD AND SCHRIEVER AVENUE.

THE TOPOGRAPHY SHOWN HEREON IS BASED ON DATA TOPOGRAPHY . FROM A GROUND SURVEY COMPLETED NOVEMBER 07,

> UNDERGROUND UTILITIES SHOWN HEREON ARE BASED UPON FIELD LOCATED ABOVE GROUND EVIDENCE AND SURFACE MARKINGS REPRESENTING DETECTED UNDERGROUND UTILITIES. RECORD UTILITIES SHOWN ARE APPROXIMATE AND ARE BASED ON CLIENT SUPPLIED AS-BUILTS. UTILITIES SHOWN HEREON MUST BE VERIFIED PRIOR TO CONSTRUCTION.

## CONTROL TABLE

KRC

\pprod.psomas.corp\panzuraprojects\ROS\_Projects\6CAL212503\SURVEY\CIVIL3D\V-AL-Mather.dwg

POINT #	NORTHING	EASTING	ELEVATION	DESCRIPTION
1001	1970407.28	6760268.66	86.10	MAG & NAIL
1002	1970256.86	6760066.08	87.87	MAG & NAIL
1006	1969874.51	6759954.17	86.70	MAG & NAIL
1007	1970065.42	6760215.20	89.25	MAG & NAIL
1100	1970650.43	6760509.43	85.35	SCRIBED X
1101	1969861.09	6759819.61	85.48	SCRIBED X
1102	1970438.90	6760090.30	86.58	SCRIBED X
1103	1970255.39	6759819.17	85.93	SCRIBED X

BNT Title Company of California Order ID: CA221049, dated May TITLE REPORT INDICATES TITLE REPORT EXCEPTION NO. The following exception items, being assessments, taxes, loans and ownership, are beyond the scope of this survey and are not addressed hereon:

(1) (2) (3) (4) (5) (6) (24)

(7) Water rights, claims or title to water, whether or not shown by the public record. EFFECT OF .. BLANKET IN NATURE

(8) Rights of the public in and to that portion of the land lying within any Road, EFFECT OF . Street, Alley or Highway. PLOTTED HEREON

Easement(s) for the purpose(s) shown below and rights incidental thereto as delineated or as offered for dedication, on the map of said tract/plat;

> Natomas American River Subdivision No. 4, Book 15, Page Мар: Private Road Purpose:

As shown on said map

Affects: PLOTTED HEREON

PLOTTED HEREON

Discrepancies, conflicts in boundary lines, shortage in area, encroachments, or any other matters shown on

> Map No: Book 40, Page 14, Record of Survey Recorded: October 11, 1985

PLOTTED HEREON Discrepancies, conflicts in boundary lines, shortage in area, encroachments, or any other matters shown on

> Map No: Book 45, Page 16, Record of Survey Recorded: June 7, 1989

Discrepancies, conflicts in boundary lines, shortage in area, encroachments, or any other matters shown on

> Book 54, Page 62, Record of Survey Map No: Recorded: February 24, 1995

PLOTTED HEREON; Surveyor's note: Referenced document incorrectly noted as 54 RS 62 instead of 54 RS 02.

The fact that said land lies within the boundaries of the Mather Air Force Base Redevelopment Project Area, as disclosed by the document recorded May 16, 1995 in Book 9505-16, Page 1857 of Official Records.

> Document declaring modification thereof recorded July 17, 2007 in Book 20070717, Page 0639 of Official Records.

Easement(s) for the purpose(s) shown below and rights incidental thereto as set

forth in a document: United States of America In favor of: Natural gas, drinking water, storm water and sanitary Purposes: sewer utility system Recorded:

May 6, 1997 199705060128, Official Records As described in said document

PLOTTED HEREON

Recording No:

Affects:

Recorded:

Recorded:

Recording No:

(14)

EFFECT OF .....

(15) Covenants, conditions and restrictions but omitting any covenants or restrictions, if any, including but not limited to those based upon race, color, religion, sex, sexual orientation, familial status, marital status, disability, handicap, national origin, ancestry, source of income, gender, gender identity, gender expression, medical condition or genetic information, as set forth in applicable state or federal laws, except to the extent that said covenant or restriction is permitted by applicable law, as set forth in the document

May 6, 1997

199705060128, Official Records Recording No: (16) Any rights incidental to the ownership and development of the mineral interest

excepted or reserved in the document Resolution Number 97-0481 and Quitclaim Deed for Entitled:

Conveyance of Real Property relating to the Mather Air Force Base Economic Development Conveyance May 6, 1997

Quitclaim Deed recorded September 10, 1997, Recording No. 199709100834 of Official Records.

199705060128, Official Records

Reference is made to said documents for full particulars. Discrepancies, conflicts in boundary lines, shortage in area, encroachments, or any other matters shown on

Book 56, Page 12, Record of Survey Map No: Recorded: August 29, 1997 PLOTTED HEREON

Easement(s) for the purpose(s) shown below and rights incidental thereto as delineated or as offered for dedication, on the map of said tract/plat; Book 56, Page 12, Record of Survey Map No: August 29, 1997 Recorded:

Drainage; Public Utility Easement; Water; Natural Gas and Purposes: Intertie Affects: All as shown on said map

EFFECT OF ..... The terms and provisions contained in the document entitled "Disposition and Development Agreement" recorded December 1, 1998 in Book 9812-01, Page 1580 of Official Records.

DOES NOT AFFECT SUBJECT PARCEL

Matters contained in that certain document EFFECT OF .....

PLOTTED HEREON

Recording No:

Resolution of Retrocession of Legislative Jurisdiction Entitled: Dated: October 22, 2012 California State Lands Commission Executed by: November 5, 2012 Recorded:

Book 20121105, Page 0050, Official Records

Reference is made to said document for full particulars. The herein described property lies within the boundaries of a Mello-Roos EFFECT OF .....

Community Facilities District (CFD) as follows:

Community Facilities District No. 2016-01 Cordova Recreation and Park District Notice of Special Tax Lien Disclosed by: December 23, 2016 Recording Date: Book 20161223, Page 0546, Official Records Recording No.: 22

Any facts, rights, interests or claims that may exist or arise by reason of the following matters disclosed to this company. A. The fact that overhead wires are located on the southwesterly portion of said B. Steel fence is across the northeasterly and southeasterly property line,

ownership of fence is unknown.

MATHER

ALTA DUE DILIGENCE SURVEY FOR: DEPARTMENT OF GENERAL SERVICES CALIFORNIA OFFICE OF EMERGENCY SERVICES **3650 SCHRIEVER AVENUE** 

DATE: 11/10/2022 N/A 6CAL212503

**BENCHMARK** 

1075 Creekside Ridge Drive, Suite 200 Roseville, CA 95678 (916) 788-8122 (916) 788-0600 (FAX)

SACRAMENTO COUNTY

CALIFORNIA

The requirement for submission to this Company of a resolution of the governing

been requested. The resolution must designate the officers authorized to execute

Unrecorded matters which may be disclosed by an Owner's Affidavit or Declaration.

transaction. Your prompt attention to this requirement will help avoid delays in the

Matters which may be disclosed by an inspection and/or by a correct ALTA/ACSM

Any rights of the parties in possession of a portion of, or all of, said Land, which

The Company reserves the right to except additional items and/or make additional

Land Title Survey of said Land that is satisfactory to the Company, and/or by

rights are not disclosed by the public records. The Company will require, for review, a full and complete copy of any unrecorded agreement, contract, license

and/or lease, together with all supplements, assignments and amendments

thereto, before issuing any policy of title insurance without excepting this item

Report/Commitment. This Affidavit/Declaration is to be completed by the record

A form of the Owner's Affidavit/Declaration is attached to this Preliminary

owner of the land and submitted for review prior to the closing of this

The Company reserves the right to add additional items or make further

requirements after review of the requested Affidavit/Declaration.

body of State of California authorizing the transaction for which this report has


on the State of California's behalf.

closing of this transaction. Thank you.

inquiry of the parties in possession thereof.

requirements after reviewing said documents.

from coverage.



### COMMENTS

COORDINATES

PURPOSE OF SURVEY THE PURPOSE OF THIS SURVEY IS TO MAP EXISTING TOPOGRAPHY AND PLANIMETRICS FOR A PORTION OF THE

PROPERTY SHOWN AND LOCATED AT 3650 SCHRIEVER AVE, MATHER, CA.

HORIZONTAL DATUM . THE HORIZONTAL DATUM FOR THIS PROJECT IS BASED UPON THE CALIFORNIA COORDINATE SYSTEM OF 1983, CCS83, ZONE 2, (2017.5 EPOCH) IN ACCORDANCE WITH THE CALIFORNIA PUBLIC RESOURCES CODE SECTIONS 8801-8819; SAID DATUM IS BASED LOCALLY UPON

FIELD-OBSERVED TIES TO THE CALIFORNIA SPATIAL REFERENCE NETWORK STATIONS P146, P230, P270, AND COORDINATE VALUES SHOWN HEREON ARE CALIFORNIA

COORDINATE SYSTEM OF 1983 (CCS83) ZONE 2 (2017.5

THE VERTICAL DATUM OF THIS MAPPING IS THE VERTICAL DATUM . NATIONAL GEODETIC VERTICAL DATUM OF 1988 (NAVD 88) BASED ON THE COUNTY OF SACRAMENTO

THE TOPOGRAPHY SHOWN HEREON IS BASED ON DATA TOPOGRAPHY FROM A GROUND SURVEY COMPLETED NOVEMBER 07, 2022.

BENCHMARK 1B-102.

EPOCH) GRID COORDINATES.

UNDERGROUND UTILITIES SHOWN HEREON ARE BASED UTILITIES .. UPON FIELD LOCATED ABOVE GROUND EVIDENCE AND SURFACE MARKINGS REPRESENTING DETECTED UNDERGROUND UTILITIES. RECORD UTILITIES SHOWN ARE APPROXIMATE AND ARE BASED ON CLIENT SUPPLIED AS-BUILTS. UTILITIES SHOWN HEREON MUST BE VERIFIED PRIOR TO CONSTRUCTION.

**TREES** THIS DOES NOT CONSTITUTE A TREE SURVEY. TREES AND DRIPLINES SHOWN HEREON HAVE BEEN LOCATED BASED ON VISIBLE SURFACE EVIDENCE ONLY. TREE SPECIES AND SIZES HAVE NOT BEEN VERIFIED BY A CERTIFIED

ARBORIST.

CONTOUR INTERVAL 1 FOOT MINORS, 5 FOOT MAJORS

MAPPING NOTE PLANIMETRIC DATA SHOWN OUTSIDE OF SURFACE BOUNDARY HAS BEEN SUPPLIED FOR VISUAL PURPOSES ONLY AND DOES NOT REPRESENT A FULL DESIGN SURVEY. WHILE THE VERTICAL DATA SHOWN IS ACCURATE, IT SHOULD NOT BE UTILIZED FOR SURFACING

PURPOSES.

### LEGEND

A SURVEY CONTROL POINT BUILDING LINE BUILDING COLUMN CONCRETE / WALL ELECTRIC CABINET CONCRETE CURB ELECTRIC TRANSFORMER — X — X — FENCE LINE POWER PULL BOX MAJOR CONTOUR LINE GP GATE POST INTERMEDIATE CONTOUR LINE H BIB HOSE BIB CONCRETE FLOWLINE MONUMENT ROAD PAINT LINE SEWER CLEANOUT EDGE OF PAVEMENT <del>-o</del> SIGN EDGE OF BUILDING SIGN POST SIGN POST AS-BUILT UNDERGROUND LINE AS NOTED TELEPHONE PULL BOX UNDERGROUND COMMUNICATIONS LINE □ TELEPHONE VAULT UNDERGROUND WATER LINE TREE SYMBOL UNDERGROUND SEWER LINE UTILITY POLE UNDERGROUND STORM DRAIN LINE WATER VALVE WATER METER UNDERGROUND ELECTRIC LINE STORM INLET UNDERGROUND CABLE TV LINE D STORM MANHOLE UNDERGROUND UNKNOWN UTILITY LINE S SANITARY SEWER MANHOLE UNDERGROUND GAS LINE <sup>BL</sup> BOLLARD

## CONTROL TABLE

■ UNKNOWN VAULT


₩ FIRE HYDRANT

🌣 LIGHT

STORM MANHOLE GRATE

POINT #	NORTHING	EASTING	ELEVATION	DESCRIPTION
1001	1970407.28	6760268.66	86.10	MAG & NAIL
1002	1970256.86	6760066.08	87.87	MAG & NAIL
1006	1969874.51	6759954.17	86.70	MAG & NAIL
1007	1970065.42	6760215.20	89.25	MAG & NAIL
1100	1970650.43	6760509.43	85.35	SCRIBED X
1101	1969861.09	6759819.61	85.48	SCRIBED X
1102	1970438.90	6760090.30	86.58	SCRIBED X
1103	1970255.39	6759819.17	85.93	SCRIBED X

## APPENDIX G



TOPOGRAPHIC SURVEY FOR:

MATHER




COUNTY OF SACRAMENTO, BM 1B-102 2" BRASS DISC STAMPED "SAC. CO. DEPT OF PUBLIC WORKS" NEAR SOUTHWEST CORNER OF THE CONCRETE BASE FOR SIGNAL STANDARD NORTH SIDE OF INTERNATIONAL DR AT INTERSECTION OF INTERNATIONAL DR AND MATHER FIELD RD.


P S O M A S Roseville, CA 95678 (916) 788-8122 (916) 788-0600 (FAX)


DEPARTMENT OF GENERAL SERVICES CALIFORNIA OFFICE OF EMERGENCY SERVICES 3650 SCHRIEVER AVENUE


SACRAMENTO COUNTY

1" = 40' 6CAL212503 CALIFORNIA













January 26, 2023

Brett Billingsley State of California 707 3<sup>rd</sup> St W Sacramento, CA 95605

Re: 3650 Schriever Ave

Dear Brett Billingsley,

Thank you for providing PG&E the opportunity to review the proposed plans for 3650 Schriever Ave dated 1/23/2023. Our review indicates the proposed improvements do not appear to directly interfere with existing PG&E facilities or impact our easement rights.

Please note this is our preliminary review and PG&E reserves the right for additional future review as needed. This letter shall not in any way alter, modify, or terminate any provision of any existing easement rights. If there are subsequent modifications made to the design, we ask that you resubmit the plans to the email address listed below.

If the project requires PG&E gas or electrical service in the future, please continue to work with PG&E's Service Planning department: <a href="https://www.pge.com/cco/">https://www.pge.com/cco/</a>.

As a reminder, before any digging or excavation occurs, please contact Underground Service Alert (USA) by dialing 811 a minimum of 2 working days prior to commencing any work. This free and independent service will ensure that all existing underground utilities are identified and marked on-site.

If you have any questions regarding our response, please contact the PG&E Plan Review Team at pgeplanreview@pge.com.

Sincerely,

PG&E Plan Review Team Land Management